




Site Specific Flood Risk Assessment

July 2022



Tionscadal Éireann
Project Ireland
2040



Iarnród Éireann
Irish Rail

Table of contents

1.	INTRODUCTION	1
1.1.	Description of Study Area.....	1
2.	FLOOD RISK	3
2.1	Identification of Flood Risk	3
2.2	Likelihood of Flooding.....	3
2.3	Definition of Flood Zones	4
2.4	Sequential Approach & Justification Test.....	4
3.	STAGE 1: FLOOD RISK IDENTIFICATION	6
3.1	General	6
3.2	Vulnerability of the Proposed Site	6
3.3	Information Sources Consulted	6
3.4	Primary Sources of Baseline Data	7
3.5	Secondary Sources of Baseline data	9
3.6	Source – Pathway – Receptor Model.....	11
3.7	Stage 1 Conclusions.....	12
3.7.1	Fluvial Flooding	12
3.7.2	Coastal Flooding	12
3.7.3	Pluvial Flooding	12
3.7.4	Surface Water Flooding.....	12
3.7.5	Groundwater Flooding.....	13
4.	STAGE 2 – INITIAL FLOOD RISK ASSESSMENT	14
4.1	General	14
4.2	Fluvial & Sea Level Rises / Coastal Flooding.....	14
4.2.1	Docklands and Newcomen.....	14
4.2.2	Leixlip Confey Station.....	14
4.2.3	XG012 Barberstown Level Crossing	15
4.2.4	Between Maynooth and Kilcock	15
4.2.5	Dunboyne Tolka River Valley	16
4.3	Surface Water.....	16
4.3.1	Broombridge Train Station	17
4.3.2	XG004 Clonsilla Level Crossing.....	17
4.3.3	Glendhu Park, Cabra, Dublin	17
4.3.4	M50-N3 Interchange, Railway and Royal Canal cross over the M50	17
4.3.5	Leixlip Louisa station	17
4.4	Conclusion of Stage 2 SFRA.....	18
5.	STAGE 3 – DETAILED SITE-SPECIFIC FLOOD RISK ASSESSMENT	19
5.1	Introduction.....	19
5.2	Barberstown Hydrological Analysis	19
5.3	Barberstown Hydraulic Model	20
5.3.1	Key Structures	21
5.3.2	Hydraulic Modelling Scenarios	21
5.4	Depot and OBG23 Jackson’s Bridge.....	22

5.4.1	Joint Probability Analysis.....	22
5.4.2	Fluvial Flow Estimation.....	23
5.5	Depot and OBG23 Jackson’s Bridge Hydraulic Model.....	27
5.5.1	Key Structures.....	27
5.5.2	Hydraulic Modelling Scenarios.....	28
5.6	Hydraulic Modelling Summary.....	31
6.	FLOOD RISK MANAGEMENT PROPOSALS	32
6.1	Dockland Station / Newcomen Area.....	32
6.2	Broombridge Train Station	32
6.3	XG012 Barberstown Level Crossing	32
6.4	Between Maynooth and Kilcock	32
6.4.1	OBG23 Jackson Bridge - Rail Track	32
6.4.2	Bailey’s Bridge - Proposed Depot Site	33
6.5	Dunboyne Tolka River Valley	34
7.	JUSTIFICATION TEST	35
7.1	Justification Test Conclusions	36
8.	SITE-SPECIFIC FLOOD RISK ASSESSMENT CONCLUSIONS.....	37

APPENDIX 1	Glossary Of Terms
APPENDIX 2	CFRAM Flood Sources
APPENDIX 3	National Indicative Fluvial Mapping
APPENDIX 4	ICPSS Flood Sources
APPENDIX 5	Irish Coastal Wave And Water Level Modelling Study And National Coastal Flood Hazard Mapping
APPENDIX 6	OPW National Flood Hazard Mapping
APPENDIX 7	Dublin City Development Plan 2016-2022, Strategic Flood Risk Assessment (SFRA)
APPENDIX 8	Fingal County Development Plan 2017 - 2023, Strategic Flood Risk Assessment (SFRA) And Barnhill Strategic Flood Risks Assessment (SFRA) October 2018
APPENDIX 9	Geological Survey Of Ireland: Teagasc Subsoil Mapping
APPENDIX 10	Dublin Pluvial Study Flood Mapping
APPENDIX 11	Hydrological Calculations
APPENDIX 12	Flood Extent Mapping
APPENDIX 13	Compensatory Storage Areas

1. INTRODUCTION

As part of the preliminary design process, Roughan & O'Donovan Consulting Engineers in association with IODM has carried out a Site-Specific Flood Risk Assessment for the DART+ West project. This report has been prepared in accordance with 'The Planning System and Flood Risk Management Guidelines for Planning Authorities' herein referred to as 'The Guidelines' as published by the Office of Public Works (OPW) and Department of Environment, Heritage and Local Government (DoHLE) in 2009. This report has been prepared to:

- Asses the flood risk to the subject site and adjacent lands as a result of the development as described in the Option Selection Report.
- Propose flood management options where applicable.

1.1. Description of Study Area

On the Maynooth and M3 Parkway Lines, DART+ will introduce electrified high capacity trains at increased frequency for all stations between Maynooth/ M3 Parkway to Dublin City Centre (40 km corridor). The overall scope of the DART+ Maynooth and City Centre project includes the following key elements of infrastructural work:

- Electrification and re-signalling of the Maynooth & M3 Parkway line from City Centre to Maynooth (40 km approx.).
- Capacity enhancements at Connolly (platforms, junctions & station modifications) to increase train numbers per hour.
- Capacity enhancements of Docklands Station to better serve all routes entering the city centre and to improve interchange with Luas.
- Closure of level crossings & and the provision of bridge crossings where required.
- Construction of a new DART Depot facility west of Maynooth Station for the maintenance and stabling of trains.
- Development of an interchange station with Metrolink at Glasnevin serving both the Maynooth Line.
- All civil engineering and bridge Studies into the development of options and the assessment the of these options and the Emerging Preferred Options for the overall scheme are currently underway.

The extents of the proposed DART+ West area are shown Figure 1-1 below. Generally, the permanent way (horizontal and vertical alignment of the 19th Century railway corridor) will not be amended as part of the scheme, thus limiting potential alterations to the existing flood regime. However, two short sections will deviate from the original alignment at Spencer Dock and in the vicinity of OBG23 Jackson's Bridge.




Figure 1-1 Proposed Development (orange line)

2. FLOOD RISK

2.1 Identification of Flood Risk

Flood risk is a combination of the likelihood of a flood event occurring and the potential consequences arising from that flood event and is then normally expressed in terms of the following relationship:

Flood risk = Likelihood of flooding x Consequences of flooding.

To fully assess flood risk an understanding of where the water comes from (i.e. the source), how and where it flows (i.e. the pathways) and the people and assets affected by it (i.e. the receptors) is required. Figure 2-1 below shows a source-pathway-receptor model reproduced from 'The Guidelines' (DEHLG-OPW, 2009).




Figure 2-1 Sources, Pathways and Receptors of Flooding

The principal sources of flooding generally are rainfall or higher than normal sea levels. The principal pathways are rivers, drains, sewers, overland flow and river and coastal floodplains. The receptors can include people, their property and the environment. All three elements as well as the vulnerability and exposure of receptors must be examined to determine the potential consequences.

The Guidelines set out a staged approach to the assessment of flood risk with each stage carried out only as needed. The stages are listed below:

- Stage I Flood Risk Identification – to identify whether there may be any flooding or surface water management issues.
- Stage II Initial Flood Risk Assessment – to confirm sources of flooding that may affect an area or proposed development, to appraise the adequacy of existing information and to scope the extent of the risk of flooding which may involve preparing indicative flood zone maps.
- Stage III Detailed Flood Risk Assessment – to assess flood risk issues in sufficient detail and to provide a quantitative appraisal of potential flood risk to a proposed or existing development or land to be zoned, of its potential impact on flood risk elsewhere and of the effectiveness of any proposed mitigation measures.

2.2 Likelihood of Flooding

The Guidelines define the likelihood of flooding as the percentage probability of a flood of a given magnitude or severity occurring or being exceeded in any given year. It is generally expressed as a return period or annual exceedance probability (AEP). A 1% AEP flood indicates a flood event that will be equalled or exceeded on average once every hundred years and has a return period of 1 in 100 years. Annual Exceedance probability is the inverse of return period as shown Table 2-1 below.

Table 2-1 Correlation Between Return Period and AEP

Return Period (years)	Annual Exceedance Probability (%)
1	100
10	10
50	2
100	1
200	0.5
1000	0.1

2.3 Definition of Flood Zones

Flood zones are geographical areas within which the likelihood of flooding is in a particular range. These are split into three categories in The Guidelines:

Flood Zone A

Flood Zone A where the probability of flooding from rivers and the sea is highest (greater than 1% or 1 in 100 for river flooding or 0.5% or 1 in 200 for coastal/tidal flooding).

Flood Zone B

Flood Zone B where the probability of flooding from rivers and the sea is moderate (between 0.1% or 1 in 1000 and 1% or 1 in 100 for river flooding and between 0.1% or 1 in 1000 or 0.5% or 1 in 200 for coastal/tidal flooding).

Flood Zone C

Flood Zone C where the probability of flooding from rivers and the sea is low (less than 0.1% or 1 in 1000 for both river and coastal/tidal flooding. Flood Zone C covers all plan areas which are not in zones A or B.

It is important to note that when determining flood zones, the presence of flood protection structures should be ignored. This is because areas protected by flood defences still carry a residual risk from overtopping or breach of defences and the fact that there is no guarantee that the defences will be maintained in perpetuity.

2.4 Sequential Approach & Justification Test

The Guidelines outline the sequential approach that is to be applied to all levels of the planning process. This approach should also be used in the design and layout of a development and the broad philosophy is shown in Figure 2.2 below. In general, development in areas with a high risk of flooding should be avoided as per the sequential approach. However, this is not always possible as many town and city centres are within flood zones and are targeted for development.




Figure 2-2 Sequential Approach (Source: The Planning System and Flood Risk Management)

The Justification Test has been designed to rigorously assess the appropriateness, or otherwise, of developments that are being considered in areas of moderate or high flood risk. The test comprises the following two processes.

- The first is the Plan-making Justification Test and is used at the plan preparation and adoption stage where it is intended to zone or otherwise designate land which is at moderate or high risk of flooding.
- The second is the Development Management Justification Test and is used at the planning application stage where it is intended to develop land at moderate or high risk of flooding for uses or development vulnerable to flooding that would generally be inappropriate for that land.

Table 2-2 Matrix of Vulnerability Versus Flood Zone to Illustrate Appropriate Development that is Required to Meet the Justification Test (Source: The Planning System and Flood Risk Management)

	Flood Zone A	Flood Zone B	Flood Zone C
Highly vulnerable development (including essential infrastructure)	Justification Test	Justification Test	Appropriate
Less vulnerable development	Justification Test	Appropriate	Appropriate
Water-compatible development	Appropriate	Appropriate	Appropriate

3. STAGE 1: FLOOD RISK IDENTIFICATION

3.1 General

This Stage 1 Flood Risk Identification includes a review of the existing information and the identification of any flooding or surface water management issues in the study area that may warrant further investigation.

3.2 Vulnerability of the Proposed Site

As per the OPW Guidelines, the proposed development is classified as “highly vulnerable” development as it comprises essential transport infrastructure. The guidelines stipulate that typically highly vulnerable developments are only appropriate within Flood Zone C (low risk areas).

3.3 Information Sources Consulted

The following information sources were consulted as part of the Stage 1 Flood Risk Identification:

Table 3-1 Information Sources Consulted

Source	Data Gathered
Primary Sources of Baseline Data	
Catchment Flood Risk Assessment and Management Study (CFRAM): www.floodmaps.ie	Fluvial, Pluvial, Coastal flooding examined
National Indicative Fluvial Maps	
Hydraulic Modelling Report- Dunboyne AFA	Fluvial flood risk emanating from the River Tolka and tributaries in the vicinity of Dunboyne
Irish Coastal Protection Strategy Study (ICPSS)	Coastal flooding nationally
Irish Coastal Wave and Water Level Modelling Study and National Coastal Flood Hazard Mapping	Coastal flooding, update to the ICPSS
OPW National Flood Hazard Mapping	OPW Records of Fluvial, Pluvial, Coastal flooding examined
Preliminary Flood Risk Analysis Report – Waterways Ireland	Flooding effecting waterways Ireland assets nationally
Dublin Pluvial Study (FloodResilienCity)	Pluvial flood mapping of Dublin
Secondary Sources of Baseline Data	
Dublin City Development Plan 2016–2022, Strategic Flood Risk Assessment (SFRA) Draft Dublin City Development Plan 2022-2028, Strategic Flood Risk Assessment (SFRA)	Fluvial, Coastal and Pluvial flooding examined
Fingal County Development Plan 2017 – 2023, Strategic Flood Risk Assessment (SFRA) and Barnhill Strategic Flood Risks Assessment (SFRA) October 2018 Draft Fingal County Development Plan 2023-2029, Strategic Flood Risk Assessment (SFRA)	Fluvial and Pluvial flooding examined
Kildare County Development Plan 2017 – 2023, Strategic Flood Risk Assessment (SFRA) Draft Kildare County Development Plan 2023-2029, Strategic Flood Risk Assessment (SFRA)	Fluvial and Pluvial flooding examined

Source	Data Gathered
Geological Survey of Ireland (GSI) Maps	GSI Teagasc subsoils map consulted to identify if alluvial sediments are shown to be present at development site that may indicate historic flooding.
Historical Maps	OSI 25" mapping assessed
News Reports	News reports published in newspapers or digital news websites.

3.4 Primary Sources of Baseline Data

(i) Catchment Flood Risk Assessment and Management Study

The development area is covered within the Eastern CFRAM study area. The CFRAM programme led by the OPW, provides a detailed assessment of flooding in areas identified as AFA's during the PFRA study. The CFRAMS assessments included for Spencer Dock flood defences. The published Final CFRAM mapping indicates that multiple locations within the development area are predicted to flood in extreme fluvial, coastal and pluvial events. These include:

- The area around the Docklands is liable to flood in extreme tidal events. There is no indication of flooding from simulated fluvial events. Flood levels at:
 - Coastal
 - 10%AEP Event = 2.67
 - 0.5%AEP Event = 3.12
 - 0.1%AEP Event = 3.35
 - Fluvial
 - 10%AEP Event = 2.45
 - 0.5%AEP Event = 2.45
 - 0.1%AEP Event = 2.45
- Leixlip Confey Station, flooding emanates from minor tributaries of the Ryewater River as they cross under the canal/railway.
- The Lyreen River and its tributaries flood between Maynooth and Kilcock directly south of the rail line.
- The Tolka river valley floods either side of the rail line at Dunboyne.
- The CFRAM mapping indicates pluvial flooding in various areas of the development lands.

The published CFRAM flood maps are reproduced in Appendix 2.

(ii) National Indicative Fluvial Maps

The indicative fluvial flood maps were finalised in December 2020. The mapping present flood extents for river reaches that were not previously modelled as part of the CFRAMS and have catchments larger than 5 km². As per the OPW the use of these maps is to “provide an indication of areas that may be prone to flooding. They are not necessarily locally accurate, and should not be used as the sole basis for defining the Flood Zones nor for making decisions on planning applications.” The mapping indicates flooding in the vicinity of various sections of the scheme including Docklands Newcomen, Barberstown and Maynooth/Kilcock.

The National Indicative Fluvial Mapping are reproduced in Appendix 3.

(iii) Hydraulic Modelling Report- Dunboyne AFA

This report summarises the hydraulic modelling work for the Dunboyne Area for Further Assessment (AFA) High Priority Watercourse (HPW) hydraulic model. The model incorporates flood relief works undertaken in the previous decade. The River Tolka and its tributaries were modelled in the vicinity of Dunboyne. Flooding is shown adjacent to the proposed rail line within the Tolka valley.

(iv) Irish Coastal Protection Strategy Study

The Irish Coastal Protection Strategy Study (ICPSS) Phase 3, undertaken by the OPW, covers coastal flooding throughout Ireland. The aims of the ICPSS were to establish extreme coastal flood levels and extents, produce coastal flood extent and flood depth maps and assess and quantify the hazard and potential risk associated with coastal erosion. Flood levels at Dublin port are stated to be:

- 0.5%AEP Event = 3.07mOD
- 0.1%AEP Event = 3.28mOD

The published ICPSS flood maps are reproduced in Appendix 4.

(v) Irish Coastal Wave and Water Level Modelling Study and National Coastal Flood Hazard Mapping

The Irish Coastal Wave and Water Level Modelling Study (ICWWS) provides an update to the Estimated Extreme Coastal Boundary Water Levels, associated with astronomical tide, storm surge and seiche/local wind set-up allowance, for the coast of Ireland, originally presented as output from the ICPSS. The ICWWS levels were used to generate National Coastal Flood Hazard Mapping flood maps indicate that sections of the development lands in the Docklands / Newcomen area are within the 10% AEP coastal flood extent. This represents the worst case scenario as any flood defences potentially protecting the coastal floodplain are not taken into account. Flood levels at Dublin port are stated to be:

- 10%AEP Event = 2.86mOD
- 0.5%AEP Event = 3.15mOD
- 0.1%AEP Event = 3.30mOD

The published Irish Coastal Wave and Water Level Modelling Study and National Coastal Flood Hazard Maps are reproduced in Appendix 5.

(vi) The Barnhill Strategic Flood Risk Assessment Study, October 2019

A Strategic Flood Risk Assessment Study was undertaken as part of the 2019 Barnhill LAP. Hydraulic modelling conducted as part of the assessment indicates that flooding emanates from the Westmanstown stream in extreme events. Flooding effects the lands to the north of canal where the proposed Barberstown bridge crossing is to be located. Flood depths in this area in a 0.1% AEP event are estimated to be 1.2 m.

(vii) OPW National Flood Hazard Mapping

The OPW National Flood Hazard Mapping Web Site (www.floodmaps.ie) was examined to identify any recorded flood events within the vicinity of the development site. Flood events have been recorded as follows:

- Dockland train station, Reports of flooding at station in July 2013 following heavy rainfall event.
- Broombridge Train Station, on 24th October 2011, Record states “The canal overflowed which may have been due to a blockage at Glasnevin. The drainage on the road was blocked or was unable to cope with the volume of water and it flowed into the station. The drains from the local housing estates are in the direction of the railway, which may have impacted on the flood.” (Floodinfo.ie). Rainfall in Dublin region on the 24th October 2011 was estimated by met Eireann to be circa a 1 in 75 year event over a 9hr period.
- Glendhu Park, Cabra, Dublin, Flood depths of 0.5m recorded on 24th October 2011. Record states “The source of the flooding is runoff from surface water drainage. Flood water appears to have built up in the Glendhu Park area. The landscaped area in front of the houses is depressed with run-off from the larger area ponding in front of properties.” The rail track was not affected.
- M50-N3 Interchange, Railway and Royal Canal bridged over the M50. M50 is indicated to have flooded multiple times due to extreme rainfall events. No indication that railway or canal flooded

at this location. Record states “Remedial measures to road drainage have been undertaken at these locations” (Fingal County Council meeting Item No. 22, 09/12/2002). No indication of flooding on the rail track.

- XG004 Clonsilla level crossing, records of historic flooding in the vicinity of the Clonsilla crossing occurring 2000-2002. Appear to have been caused by inadequate capacity in existing drainage. No evidence that flooding effected level crossing or track.
- The Lyreen River Flood Relief Scheme, Preliminary Report indicates flooding on the rail track at Jackson Bridge and on site of the proposed depot at Bailey’s Bridge in November 2000. The extreme event was calculated to be approximately a 1 in 70 years event. Aerial photos show ponding water on these lands.

An overview of OPW Flood Hazard record locations is reproduced in Appendix 6.

3.5 Secondary Sources of Baseline data

The following sources were also examined to identify areas that may be liable to flooding:

(i) Dublin City Development Plan 2016–2022, Strategic Flood Risk Assessment (SFRA)

The SFRA was developed to inform the Dublin City Development Plan 2016–2022 and compiles multiple different sources of flood information for DCC lands.

The SFRA indicates that the area surrounding the Docklands Station is defended up to the 1% AEP fluvial and 0.5% AEP coastal flood events.

The Strategic Flood Risk Assessment Mapping is reproduced in Appendix 7.

(ii) Draft Dublin City Development Plan 2022–2028, Strategic Flood Risk Assessment (SFRA)

The SFRA indicates that the area surrounding the Docklands Station is defended up to the 1% AEP fluvial and 0.5% AEP coastal flood events.

(iii) Fingal County Development Plan 2017–2023, Strategic Flood Risk Assessment (SFRA)

XG012 Barberstown Level Crossing

Indications of flooding at Westmanstown stream (Barnhill Stream) culvert under the canal/railway and downstream. Proposed crossing is within the area indicated as liable to flood.

The Strategic Flood Risk Assessment Mapping is reproduced in Appendix 8.

(iv) Draft Fingal County Development Plan 2023–2029, Strategic Flood Risk Assessment (SFRA)

XG012 Barberstown Level Crossing

Indications of flooding at Westmanstown stream (Barnhill Stream) culvert under the canal/railway and downstream. Proposed crossing is within the area indicated as liable to flood.

A simplified assessment of flooding emanating from the Royal canal as a result of overtopping or failure of the embankment is presented. The existing rail line is within the “indicative inundation boundary”, SFRA figure is reproduced in Figure 3-1 below. It is noted that the flood extents shown were not numerically modelled but instead they are the result of a topographic analysis showing lands lower than the canal bank. No indication of historic flooding emanating from the canal is presented for this location.



Figure 3-1 Possible Inundation Area of the Royal Canal

(v) Kildare County Development Plan 2017–2023, Strategic Flood Risk Assessment (SFRA)

Development area was not covered as part of the Kildare County Development Plan 2017 – 2023 SFRA.

(vi) Draft Kildare County Development Plan 2023–2029, Strategic Flood Risk Assessment (SFRA)

Development area was not covered as part of the Draft Kildare County Development Plan 2023-2029 SFRA.

(vii) GSI Maps

GSI Teagasc subsoils map shows the multiple areas within the development lands are underlain by Alluvial materials indicating the locations of historic floodplains. Notable locations include Barberstown crossing and the proposed depot site. Refer to Appendix 9 for GSI maps.

(viii) Historical Maps

Historic maps were studied. No areas of the site have been identified as liable to flooding.

(ix) News Reports

The following reports describe flooding within the proposed development lands:

- Irish Times, July 2013, Flooding occurred at Croke park, but no flooding of the rail track was reported. Available at: <https://www.irishtimes.com/news/ireland/irish-news/croke-park-open-for-qualifiers-despite-flash-flooding-yesterday-1.1477419>

(x) Preliminary Flood Risk Analysis Report – Waterways Ireland

This report looks at the possible flooding mechanisms arising from Waterways Ireland Assets an analysis of historic flooding and potential future flooding of the canal systems within the Island of Ireland. The most significant flooding of the Royal Canal was in the Spencer Dock area in Dublin city in 2002 when, due to the very high tide levels, the River Liffey was 0.4 m higher than the level in the Royal Canal. Occasional flooding has also happened at Maynooth Harbour of one adjacent garden “if sluices in the lock gates are not left in the correct position”.

(xi) Dublin Pluvial Study (FloodResilienCity)

This involved the development of a pluvial flood risk management strategy for Dublin, based on modelling and mapping of Dublin’s pluvial flood risk. Mapping shows localised pluvial flooding throughout Dublin City. The Dublin Pluvial Study flood maps are reproduced in Appendix 10.

3.6 Source – Pathway – Receptor Model

The following source-pathway-receptor model has been developed using the information examined in the Stage I Flood Risk Identification to categorise the sources of flooding, where it flows to (pathway) and the people and infrastructure affected by it (receptors). The likelihood and consequences of each type of flooding have also been assessed to determine the risk. These are summarised in the tables below.

Table 3-2 Fluvial Source-Pathway-Receptor Model

Source	Pathway	Receptor	Likelihood	Consequence	Risk
Fluvial flooding	Overbank flow from the Liffey River at Dockland Train station	Proposed Docklands Train station	Low	High	Moderate
	Overbank flow from river Tolka at rail track north of Dockland Train Station	Rail Track	Low	High	Moderate
	Overbank flow from Lyreen River at Jackson Bridge	Rail Track	High	High	High
	Overbank flow from Lyreen River at proposed Depot	Rail Track	High	High	High
	Overland flow from Westmanstown Stream at Barberstown level crossing	Proposed Bridge / Road	High	Moderate	High

Table 3-3 Coastal Source-Pathway-Receptor Model

Source	Pathway	Receptor	Likelihood	Consequence	Risk
Coastal flooding	Overbank flow from Liffey / Tolka estuaries caused by high tides	Dockland Train Station / rail line at Newcomen	Moderate	High	High

Table 3-4 Pluvial Source-Pathway-Receptor Model

Source	Pathway	Receptor	Likelihood	Consequence	Risk
Pluvial flooding	Extreme rainfall events	Dockland Train Station and surrounding area	Moderate	Low	Moderate
	Extreme rainfall events	Lands designated for Depot	Moderate	Low	Low
	Extreme rainfall events	Ashtown Canal Underpass	Moderate	Moderate	Moderate

Table 3-5 Surface Water Source-Pathway-Receptor Model

Source	Pathway	Receptor	Likelihood	Consequence	Risk
Surface Water Drainage Network Flooding	Flooding from surface water drainage network and overbank flow from Royal Canal	Broombridge Train Station; Rail Track	Low	High	Moderate
	Extreme rainfall events & flooding from surface water drainage network	Lands in the vicinity of Clonsilla Level Crossing	Moderate	Low	Low

Source	Pathway	Receptor	Likelihood	Consequence	Risk
	Extreme rainfall events & flooding from surface water drainage network	Glendhu Park, Cabra, adjacent to railway track	Moderate	Low	Low
	Extreme rainfall events & flooding from surface water drainage network	M50-N3 Interchange, Railway and Royal Canal cross over the M50	Moderate	Moderate	Moderate
	Royal Canal overtopping or embankment failure	Rail Track at Barberstown Level Crossing	Low	High	Moderate

3.7 Stage 1 Conclusions

3.7.1 Fluvial Flooding

A number of sources including the CFRAM maps and the SFRA for the Dublin City Development Plan 2016–2022 and Fingal Development Plan 2017–2023 indicate that the following areas may be at risk of fluvial flooding:

- Leixlip Confey Station/
- Barberstown (XG012) Level Crossing/
- Between Maynooth and Kilcock/
- Dunboyne Tolka River Valley/

Therefore, a Stage 2 – Initial Fluvial Flood Risk Assessment is required for the development.

3.7.2 Coastal Flooding

The SFRA for the Dublin City Development Plan 2016–2022, the ICPSS and the ICWWS indicate a risk of flooding to the development area in events => 0.2%AEP event in the Docklands / Newcomen Area. Therefore, a Stage 2 – Initial Coastal Flood Risk Assessment is required for the development.

3.7.3 Pluvial Flooding

Pluvial flooding results from heavy rainfall that exceeds ground infiltration capacity or more commonly in Ireland where the ground is already saturated from previous rainfall events. This causes ponding and flooding at localised depressions. Pluvial flooding is commonly a result of changes to the natural flow regime such as the implementation of hard surfacing and improper drainage design. Although various locations within the development have been identified as potentially at risk from pluvial flooding, the implementation of SuDS throughout the scheme is seen as sufficient to mitigate this risk. Therefore, the risk of pluvial flooding is classified as low and no further assessment is required.

3.7.4 Surface Water Flooding

Surface water flooding occurs when the local drainage system cannot convey stormwater flows from extreme rainfall events. The rainwater does not drain away through the normal drainage pathways or infiltrate into the ground but instead ponds on or flows over the ground. Surface water flooding is unpredictable as it depends on a number of factors including ground levels, rainfall and the local drainage network. Multiple sources indicate historical surface water flooding at the following locations in the study area:

- Broombridge Train Station.
- XG004 Clonsilla Level Crossing.
- Glendhu Park, Cabra, Dublin.

- M50-N3 Interchange, Railway and Royal Canal cross over the M50.

Therefore, a Stage 2 – Initial Surface Water Flood Risk Assessment is required for the development.

Regarding flooding emanating from the Royal Canal at Barberstown as a result of overtopping or embankment failure. Given that there is no indication of historic flooding as a result of overtopping the canal at this location and the assumption that the canal/railway embankment will be maintained during the operational lifespan of the above infrastructure, the risk of flooding from this source is classified as low and no further assessment is required.

3.7.5 Groundwater Flooding

Ground water flooding is a result of upwelling in occurrences where the water table or confined aquifers rises above the ground surface. This tends to occur after long periods of sustained rainfall and/or very high tides. High volumes of rainfall and subsequent infiltration to ground will result in a rising of the water table. Groundwater flooding tends to occur in low-lying areas, where with additional groundwater flowing towards these areas, the water table can rise to the surface causing groundwater flooding. No indication of historic or predicted groundwater flooding was identified within the study area. Therefore, the risk of groundwater flooding is classified as low and no further assessment is required.

4. STAGE 2 – INITIAL FLOOD RISK ASSESSMENT

4.1 General

The Stage 2: Initial Flood Risk Assessment will confirm the sources of flooding that may affect the proposed development site, appraise the adequacy of existing information and scope the requirements of the Stage 3 Detailed Flood Risk Assessment.

4.2 Fluvial & Sea Level Rises / Coastal Flooding

Stage 1 identified fluvial and coastal flooding at the following locations:

- Docklands / Newcomen Area.
- Leixlip Confey Station, flooding emanates from minor tributaries of the Ryewater River as they cross under the canal/railway.
- Barberstown (XG012) Level Crossing.
- Between Maynooth and Kilcock, River Lyreen flooding.
- Dunboyne Tolka River Valley.

4.2.1 Docklands and Newcomen

The Docklands/Newcomen area is in close proximity to the Liffey, Tolka and Royal Canal. The Tolka and Liffey are tidally dominated at this location, as such; the most prevalent flood risk to the site is from extreme tidal inundation events or tidal events in combination with extreme fluvial events. Hydraulic modelling undertaken as part of the ICWWS indicates that the subject site is liable to flood from tidal inundation in the 0.5%AEP event. However, it should be noted that the aforementioned assessments do not account for flood defence infrastructure. As such the measures along the Tolka's estuary and works at Spencer dock are not considered. In comparison, the CFRAMS (2017) flood mapping does take account of these measures and no flooding indicated within the development site in the 0.1% AEP coastal event. As per The Guidelines the Docklands / Newcomen area is within Flood Zone A. However, when existing flood risk management measures are considered the lands are defended to the design standard 0.5% AEP coastal flood event and the 0.1% AEP event when freeboard allowances are accounted for.

Both the ICWWS and CFRAMS considered the likely effects of climate change. With the inclusion of climate change factors (as per the OPW Mid-Range Future climate scenario) both studies show that the development lands are liable to flood in the 0.5% AEP event and much of the land is liable to have flood depths of >2m above existing ground levels. The ICWWS estimated flood levels at Spencer Dock incorporating climate change are:

- 10% AEP (+MRFS) Event = 3.36OD
- 0.5% AEP (+MRFS) Event = 3.58mOD
- 0.1% AEP (+MRFS) Event = 3.80mOD

Track lowering is proposed at multiple locations in this area to accommodate the OHLE that is required for electrification of the line in addition to the provision of underground platforms at Docklands Station. In future extreme events exacerbated by climate change there is potential for subject lands to be inundated from tidal flooding including the underground platforms. Refer to section 6 of this report for proposed flood risk management measures.

4.2.2 Leixlip Confey Station

Flooding emanates from minor tributaries of the Ryewater River (the Rathleek and Sillechain streams) as they cross under the canal/railway. CFRAMS mapping indicates that the two culverts conveying the streams

under the Royal canal and railway act as a minor restriction to flow in the fluvial 0.1%AEP event. Flooding remains north of the canal in these events and does not encroach on rail infrastructure in the area. As per The Guidelines Leixlip Confey station and the adjacent rail infrastructure are within Flood Zone C.

CFRAMS mapping indicates that when climate change is considered (MRFS), flood waters flow along the canal in an easterly direction. Confey station is protected by a >1 m wall/embankment along its length while the track extending east and west is similarly elevated. It is highly unlikely that flood waters could build up within the canal as to inundate the rail line to the south. The information available is considered sufficient to appraise flood risk at Leixlip Confey area and further assessment is not required.

4.2.3 XG012 Barberstown Level Crossing

The proposed Barberstown bridge crossing is indicated to be within the 1%AEP flood extents (Barnhill LAP SFRA) of the Westmanstown stream. Flooding appears to be caused by insufficient capacity of the culvert which conveys the watercourse under the canal and railway. Irish rail have indicated that works have been undertaken subsequent to the Barnhill LAP SFRA to remove the flow constriction present in the canal/railway culvert. The effect of these works on flooding has not been quantified. The proposed bridge at Barberstown is considered to require a stage 3 detailed flood risk assessment with respect to inundation derived from fluvial flooding.

4.2.4 Between Maynooth and Kilcock

There are three distinct flooding locations between Maynooth and Kilcock. These are:

4.2.4.1 Maynooth Train station

The Meadowbrook stream is culverted (UBG21A) under that Royal canal and railway approximately 400 m west of Maynooth train station. Flood mapping undertaken as part of the CFRAM study indicates that in extreme events flooding occurs south of the rail line and floods an area of residential properties and adjacent road network. A small area of ponding along the rail line at Bond bridge (OBG21) in the 0.1% AEP event. This area is confined to the low point at bond bridge and does not extend to the train station. As per The Guidelines Maynooth station and the adjacent rail infrastructure are within Flood Zone C.

CFRAMS mapping indicates that when climate change is considered (MRFS), the station and rail line is not affected in the 1% AEP event, however the 0.1% AEP event is shown to cause significant flooding of a large area of Maynooth south of the rail line.

The information available is considered sufficient to appraise flood risk at Maynooth Train Station and further assessment is not required. Refer to section 6 of this report for proposed flood risk management measures.

4.2.4.2 Jackson Bridge - Rail Track

The area directly south of the royal canal between Maynooth and Kilcock has a history of flooding and has been subject to CFRAMS hydraulic assessment reflecting the same. The Lyreen River flows under the canal and railway via an inverted syphon (UBG22) ~100 m south east of Jacksons Bridge (OBG23). UBG22 appears to have insufficient capacity and causes flooding upstream, inundating the tracks and area proposed for the depot. This appears to occur in relatively frequent events (<=10% AEP). Jacksons bridge is a local low point and according to the CFRAMS, floodwaters are likely to reach track level in a 10% AEP event and reach ~400 mm in depth in a 0.1% event. CFRAMS flood levels including an allowance for climate change are not publicly available at this location but it is anticipated that these would increase significantly. The sites at Jackson Bridge are considered to require a stage 3 detailed flood risk assessment with respect to fluvial flooding.

4.2.4.3 Bailey's Bridge - Proposed Depot Site

Further north-west of Jackson bridge at Bailey's Bridge (the location of the proposed depot) OPW flood records (in the form of post flood aerial photography) indicate that this area is also liable to flood from a

minor watercourse (Ballycaghan stream) that was not modelled as part of the CFRAMS. Given the history of flooding and lack of information available for the area, the proposed depot lands are considered to require a stage 3 detailed flood risk assessment with respect to fluvial flooding.



Figure 4-1 Flooding south of Bailey's bridge November 2000

4.2.5 Dunboyne Tolka River Valley

The Tolka river valley is crossed multiple times by the railway. The area was subject to a flood alleviation scheme completed circa 2015 which upgraded many of the previous rail and road crossing of the Tolka that restricted flow. A hydraulic assessment of the completed measures was undertaken in 2019. The resultant flood extent mapping indicates that there is significant flooding of Tolka valley either side of rail line in flood events as frequent as 1 in 10 year. However, no flooding is indicated for the rail line between Bennetstown and Dunboyne including Dunboyne and the M3. A review of the flood levels and track levels indicates that in a 1 in 1000 year flood event the tracks are a minimum of 1.4 m above flood level. As per The Guidelines the rail line from Dunboyne to the M3 Parkway is considered to be within Flood Zone C.

The climate change mapping for the area shows no indication flooding of the track or M3 Parkway in the 0.1%AEP + MRFS event. The information available is considered sufficient to appraise flood risk at the Dunboyne Tolka River Valley and no further assessment is required. Refer to section 6 of this report for proposed flood risk management measures.

4.3 Surface Water

Stage 1 identified potential surface water flooding issues at the following locations:

- Broombridge Train Station.
- XG004 Clonsilla Level Crossing.
- Glendhu Park, Cabra, Dublin.
- M50-N3 Interchange, Railway and Royal Canal cross over the M50.
- Louisa station, Leixlip.

4.3.1 Broombridge Train Station

As described in the OPW flood event report, flooding at Broombridge Train Station on 24th October 2011 appears to have been caused by extreme rainfall in combination with a series of blockages in the surface water drainage network and Royal Canal. Met Eireann indicated that the 9hr storm event on the 24th October was circa 1.3% AEP at the Phoenix Park gauge. The OPW indicates that road drainage may have become blocked or had its capacity exceeded. As there is no evidence of previous or subsequent flooding at this location the flood risk is considered low.

There is no indication of coastal or fluvial contributions to flooding at this location therefore as per the Guidelines Broombridge Train Station and the adjacent rail infrastructure are within Flood Zone C. The information available is considered sufficient to appraise flood risk at the Broombridge Train Station and no further assessment is required.

4.3.2 XG004 Clonsilla Level Crossing

Flooding has been recorded in the vicinity of the Clonsilla crossing, occurring between 2000-2002. This appears to have been caused by inadequate capacity in the existing drainage network. Subsequently, the Local Authority proposed a series of interim measures which were to be carried out in 2003. As there is no evidence of previous or subsequent flooding at this location the flood risk is considered low.

There is no indication of coastal or fluvial contributions to flooding at this location therefore as per the Guidelines Clonsilla Level Crossing and the adjacent rail infrastructure are within Flood Zone C. The information available is considered sufficient to appraise flood risk at Clonsilla Level Crossing and no further assessment is required.

4.3.3 Glendhu Park, Cabra, Dublin

The flooding in Glendhu Park in October 2011 appears to be caused by extreme rainfall. Nonetheless, DCC post-flooding reports indicate that the SuDS based drainage system performed well and minimal property damage occurred. Flood depths of ~0.5 m were recorded following this event. Given that the railway is >1 m above Glendhu Park and the adjoining lands and as there is no indication of historic or likely flooding impacts arising from the development at this location the flood risk is considered low.

There is no indication of coastal or fluvial contributions to flooding at this location therefore as per the Guidelines Glendhu Park and the adjacent rail infrastructure are within Flood Zone C. The information available is considered sufficient to appraise flood risk at Glendhu Park and no further assessment is required.

4.3.4 M50-N3 Interchange, Railway and Royal Canal cross over the M50

The railway and canal are bridged over the M50 at this location. Flooding on the 13/11/2002 appears to be solely confined to the carriageway due to the hydraulic capacity of the surface water drainage network. As there is no indication of historic or likely flooding impacts to the development at this location, this location is considered low risk.

There is no indication of coastal or fluvial contributions to flooding at this location therefore as per the Guidelines the M50-N3 Interchange and the adjacent rail infrastructure are within Flood Zone C. The information available is considered sufficient to appraise flood risk at the M50-N3 Interchange and no further assessment is required.

4.3.5 Leixlip Louisa station

Irish Rails IAMS datasets indicate historic flooding from drainage in the vicinity of the Leixlip Louisa Station. Nevertheless, there is no indication that the track was previously affected or if flooding has recurred. There

is no indication of coastal or fluvial contributions to flooding at this location therefore as per the Guidelines the Leixlip Louisa station and the adjacent rail infrastructure are within Flood Zone C. The information available is considered sufficient to appraise flood risk at the Leixlip Louisa station and no further assessment is required.

4.4 Conclusion of Stage 2 SFRA

The available sources consulted above indicate that discreet sections of the development lands are liable to flood in extreme events. Existing available information is not sufficient to provide a quantitative appraisal of flood risk to the proposed development at these locations. As per the OPW Guidelines, a Stage 3 detailed flood risk assessment is required to be undertaken to confirm flood risk (water levels and flood extents) to the proposed development. Further assessment is required at:

- Barberstown (XG012) Level Crossing.
- Between Maynooth and Kilcock.

5. STAGE 3 – DETAILED SITE-SPECIFIC FLOOD RISK ASSESSMENT

5.1 Introduction

Stages 1 and 2 of the flood risk assessment for the proposed development have indicated that a series of discrete sections of the scheme are subject to flooding in high probability exceedance events from fluvial sources. Hydraulic models have been prepared to ascertain the effects of extreme fluvial flood events at these locations. This section outlines the hydrological and hydraulic analysis undertaken.

5.2 Barberstown Hydrological Analysis

Ungauged Flow estimation

No gauging data is available for the Westmanstown stream. Flow was estimated for the catchment up to the railway canal culvert shown in Figure 5-1 below. Upstream catchment area of 6.61 km².




Figure 5-1 Westmanstown Stream Catchment for Hydrological Assessment

The peak fluvial flows for the 10% AEP, 1% AEP and 0.1% AEP events were estimated for the catchment using a series of industry standard flow estimation methods including:

- Flood Studies Report.
- Flood Studies Report 3 variable.
- Flood Studies Supplementary Reports No. 6.
- Institute of Hydrology Report 124.
- FSU Small Catchments Method.

The various methods are generally in agreement which FSSR.6, IH124 and FSU Small Catchments usually the most suitable for small catchments such as the subject area. As per the precautionary principle the FSU Small Catchment flows became the design flows. Hydrograph generation was undertaken using the FSSR16 methodology. Input parameters for flow estimation and hydrograph generation for the Westmanstown Stream are presented in Appendix 11.

Table 5-1 Barberstown Flow Estimation Results

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Barberstown	Q2	1.551	1.787	1.486	1.664	1.817
	Q5	1.959	2.257	1.877	2.101	2.296
	Q10	2.237	2.577	2.143	2.399	2.621
	Q50	2.841	3.273	2.721	3.047	3.329
	Q100	3.200	3.687	3.065	3.432	3.750
	Q200	3.494	4.025	3.347	3.747	4.094
	Q1000	4.474	5.154	4.285	4.798	5.242

In addition to the current climate scenario, flows were estimated for the Mid-Range Future Scenario (MRFS) climate change scenarios as stated in the OPW's 2019 Climate Change Sectoral Adaptation Plan.

Barberstown Summary of ROD Hydrological Assessment

Design flows for the Westmanstown Stream are stated in 5.2 below.

Table 5-2 Design Flows for Catchments for the Westmanstown stream.

Annual Exceedance Probability	Current Climate Scenario (m ³ /s)	Climate Change Scenario (m ³ /s)
50% AEP (Qmed)	1.81	2.18
10%AEP	2.62	3.14
1%AEP	3.75	4.50
0.1%AEP	5.24	6.29

5.3 Barberstown Hydraulic Model

A 1D-2D hydraulic model of the Westmanstown stream and subject lands was developed using the Flood Modeller software v5.0. A digital terrain model (DTM) of the subject lands was created using LiDAR data with cells at 5 m centres. The DTM was linked to the 1D model using a series of link lines that allow water to pass from the 1D domain to the 2D domain when the water level in the channel exceeds the bank levels. The DTM used in the hydraulic model is shown in Figure 5-2 below.



Figure 5-2 Barberstown LiDAR Derived Digital Terrain Model

A site visit was conducted on the 26th March 2020. Significant features within the channels and in the floodplains were recorded. The site visit aided in determining the manning's roughness values attributable to the reach. A roughness grid was applied in the model to represent the effects of different surfaces on overland flow. The Manning's N values for the 2D domain was seen to be agricultural grassland and represented with a N value of 0.036.

5.3.1 Key Structures

Previous hydraulic modelling undertaken as part of the Barnhill LAP SFRA indicated that the canal culvert (UBG12B) was a key restriction to flow and caused flooding upstream. The restriction was identified as an extension to the existing culvert. Irish Rail have subsequently confirmed that the undersized extension has been replaced by an extension equal in capacity to the existing culvert. This was surveyed as part of the scheme and included in the model.

5.3.2 Hydraulic Modelling Scenarios

Variations of the hydraulic model were constructed to simulate the existing site conditions for the 10% AEP, 1% AEP and 0.1% AEP events in the current and MRFS climate scenarios. In the current climate scenario no flooding is seen in to emanate from the channel in the current climate scenario up to the 0.1% AEP event. In the 0.1% AEP event, flooding exits the channel upstream of the local road culvert and ponds in the adjacent lands before flooding the road and re-entering the stream via parallel road drains. Minor flooding is also seen in the drainage that runs parallel to the channel from the west.

In the climate change scenario, flooding is also very limited with the only minor flooding of lands north of the subject area up to the 0.1% AEP event. In the 0.1% AEP MRFS event the area north of the local road continues to flood. In addition, the lands immediately upstream of the canal culvert appear to flood with waters going out of bank for ~160 m upstream of the culvert. Nonetheless, none of the modelled scenarios were seen to affect the proposed road layout and bridge abutment proposed for the site. The model indicates none of the proposed development footprint is within the 0.1% AEP flood extents (including climate change) and therefore, the development at Barberstown is within Flood Zone C. The Barberstown hydraulic model flood extents are shown in Appendix 12.

Water Level Results

Table 5.3 details the calculated extreme water levels at key locations exported from the hydraulic model.

Table 5-3 Water levels Summary

	Climate	Current Scenario (CS)			
	Development	Current		MRFS	
	AEP	1%	0.1%	1%	0.1%
Node Label	Description	mOD			
SOUTH00650	Upstream of local access road	56.84	57.05	56.97	57.1
barAli220	220m upstream of canal culvert	55.82	56.34	56.07	56.66
barAli020	20m upstream of canal culvert	55.59	56.24	55.92	56.6
SOUTH00200	100m south of canal culvert	55.13	55.42	55.29	55.55

5.4 Depot and OBG23 Jackson's Bridge

5.4.1 Joint Probability Analysis

The Depot and OBG23 locations were examined to determine the relative dependencies of watercourses in the study area. Guidance from the Flood Studies Update Work Package 3.4 (Guidance for River Basin Modelling) indicates parameters from which to determine the dependency between the Lyreen and its tributaries. These parameters are compared against the subject catchments in Table 5-4 below.

Table 5-4 Depot / OBG23 Joint Probability Analysis Dependencies

Catchment	Connected	Difference of BFI within 0.3	Centroids within 25 km	Ratio of AREA within a factor of 2.7	Difference of FARL within 0.07	Comment
Lyreen - OBG23 Model						
B	TRUE	TRUE	TRUE	FALSE	TRUE	Connected, near, AREA different, others similar
C	TRUE	TRUE	TRUE	FALSE	TRUE	Connected, near, AREA different, others similar
D	TRUE	TRUE	TRUE	FALSE	TRUE	Connected, near, AREA different, others similar
Ballycaghan Stream - Depot Model						
A	FALSE	TRUE	TRUE	FALSE	TRUE	Unconnected, near, AREA different, others similar
C	FALSE	TRUE	TRUE	TRUE	TRUE	Unconnected, near, others similar
D	TRUE	TRUE	TRUE	FALSE	TRUE	Connected, near, AREA different, others similar

5.4.2 Fluvial Flow Estimation

Extreme Value Analysis

AMAX flow data was obtained for the Maynooth (Lyreen 09049) gauging station for 20 years from 2001 – 2021. The gauge is located approximately 2.7 km downstream of UDG22 and 0.5 km upstream of the Lyreen’s confluence with the Ryewater River. A review of the gauging station based on 10 years of Amax data was undertaken as part of the Eastern CFRAMS which concluded that the Maynooth station gauge was unreliable at flood flows. Table 5-5 lists the station reference and location.

Table 5-5 OPW Hydrometric Station

Station No.	River	Station Name	Easting	Northing
09049	Lyreen	Maynooth	294081.00	238424.00

An extreme value analysis was undertaken for the available data. The calculations are given in Appendix 11 and the results are summarised in the Table 5-6 below. The highest Amax flow estimated at the Maynooth gauging station was 15.5 in 2017. The gauge has known issues that limit its applicability at high flows in the form of multiple restrictions to flow upstream including the UDG22 canal culvert.

Table 5-6 Extreme Value Analysis - Gumbel

Annual Exceedance Probability	Estimated flow (m ³ /s)
50%AEP (Qmed)	9.76
10%AEP	13.65
1%AEP	18.50
0.1%AEP	23.27

Flow estimation Comparison

Flow estimation was undertaken at 4no. locations on the Rivers Lyreen, Ballycaghan Stream and their tributaries as shown in Figure 5-3 below.




Figure 5-3 Subject Catchments for Hydrological Assessment at Depot / Jackson’s Bridge

The peak fluvial flows for the 10%, 1% AEP and 0.1% AEP events were estimated for the for each catchment using a series of industry standard flow estimation methods including:

- Flood Studies Report.
- Flood Studies Report 3 variable.
- Flood Studies Supplementary Reports No. 6.
- Institute of Hydrology Report 124.
- OPW FSU Portal.
- FSU Small Catchments Method.

Estimated flows for each catchment are shown in Table 5-7, Table 5-8, Table 5-9 and Table 5-10 below.

Table 5-7 Catchment A Flow Estimation Results

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)					
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Flood Studies Update	CFRAMS (NAM)
Lyreen Catchment A	Q2	8.959	12.700	9.171	11.199	9.07	7.77
	Q5	11.317	16.042	11.584	14.146	12.52	11.07
	Q10	12.920	18.315	13.225	16.150	14.78	13.52
	Q50	16.409	23.261	16.797	20.511	19.68	20.32
	Q100	18.484	26.202	18.921	23.105	21.86	23.98
	Q200	20.182	28.608	20.658	25.226	23.94	28.22
	Q1000	25.840	36.630	26.450	32.299	28.75	40.950

Table 5-8 Catchment B Flow Estimation Results

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment B	Q2	1.695	1.890	1.679	1.847	2.028651045
	Q5	2.141	2.387	2.121	2.334	2.562506583
	Q10	2.444	2.726	2.422	2.664	2.925528349
	Q20	2.748	3.064	2.722	2.995	3.288550115
	Q50	3.104	3.462	3.076	3.384	3.715634545
	Q100	3.497	3.899	3.465	3.812	4.185427419
	Q200	3.818	4.257	3.783	4.162	4.569803406
	Q1000	4.889	5.451	4.843	5.328	5.851056698

Table 5-9 Catchment C Flow Estimation Results

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment C	Q2	1.164	1.732	1.122	1.615	2.663758369
	Q5	1.471	2.188	1.418	2.040	3.364747414
	Q10	1.679	2.498	1.618	2.329	3.841419964
	Q20	1.887	2.808	1.819	2.618	4.318092514
	Q50	2.132	3.173	2.055	2.958	4.87888375
	Q100	2.402	3.574	2.315	3.332	5.495754109
	Q200	2.623	3.902	2.528	3.638	6.000466221
	Q1000	3.358	4.996	3.237	4.658	7.682839928

Table 5-10 Catchment D Flow Estimation Results

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment D	Q2	0.368	0.400	0.384	0.390	0.542906813
	Q5	0.464	0.505	0.485	0.493	0.685777026
	Q10	0.530	0.576	0.554	0.563	0.782928772
	Q20	0.596	0.648	0.623	0.633	0.880080517
	Q50	0.673	0.732	0.703	0.715	0.994376688
	Q100	0.758	0.825	0.792	0.805	1.120102476
	Q200	0.828	0.900	0.865	0.879	1.22296903
	Q1000	1.060	1.153	1.108	1.126	1.565857543

Estimates for catchment A (the main Lyreen catchment) are relatively disparate in their estimation of Q_{med} with a difference of 60% between the minimum and maximum estimates. As per the precautionary principle the CFRAMS (NAM) flows became the design flows. Hydrograph generation was undertaken using the FSSR16 methodology. Input parameters for flow estimation and hydrograph generation for the River Lyreen are presented in Appendix 11.

When catchment B, C & D are considered the various estimation methodologies are generally in agreement with the FSSR.6, IH124 and FSU Small Catchments usually the most suitable for small catchments such as the subject area. As per the precautionary principle the FSU Small Catchment flows became the design flows for these catchments. Hydrograph generation was undertaken using the FSSR16 methodology. Input parameters for flow estimation and hydrograph generation for the catchments B, C & D are presented in Appendix 11.

Depot / Jackson’s Bridge Summary of ROD Hydrological Assessment

Design Flows are presented in Table 5-11 below in line with the results of the joint probability analysis and flow estimation exercise.

Table 5-11 Design Flows for Catchments at OBG23 Jacksons Bridge and Depot site in current climate and climate change scenario.

Catchment	Inflow RP	Peak Flow	Catchment	Inflow RP	Peak Flow
OBG23 Simulations			Depot Simulations		
Q10			Q10		
A	Q10	13.52	A	Q2	7.77
B	Q2	2.03	B	Q10	2.93
C	Q2	2.66	C	Q2	2.66
D	Q2	0.54	D	Q2	0.54
Q100			Q100		
A	Q100	23.98	A	Q10	13.52
B	Q20	3.29	B	Q100	4.19
C	Q20	4.32	C	Q20	4.32
D	Q20	0.88	D	Q20	0.88
Q1000			Q1000		
A	Q1000	40.95	A	Q50	20.32
B	Q100	4.19	B	Q1000	5.85
C	Q100	5.50	C	Q100	5.50
D	Q100	1.12	D	Q100	1.12
OBG23 Simulations + Climate Change Allowance			Depot Simulations + Climate Change Allowance		
Q10+CC			Q10+CC		
A	Q10	16.22	A	Q2	9.32
B	Q2	2.43	B	Q10	3.51
C	Q2	3.20	C	Q2	3.20
D	Q2	0.65	D	Q2	0.65
Q100+CC			Q100+CC		
A	Q100	28.78	A	Q10	16.22
B	Q20	3.95	B	Q100	5.02
C	Q20	5.18	C	Q20	5.18
D	Q20	1.06	D	Q20	1.06
Q1000+CC			Q1000+CC		
A	Q1000	49.14	A	Q50	24.38

Catchment	Inflow RP	Peak Flow	Catchment	Inflow RP	Peak Flow
B	Q100	5.02	B	Q1000	7.02
C	Q100	6.59	C	Q100	6.59
D	Q100	1.34	D	Q100	1.34

5.5 Depot and OBG23 Jackson's Bridge Hydraulic Model

A 1D-2D hydraulic model of the subject lands was developed using the Flood Modeller software v5.0. A digital terrain model (DTM) of the subject lands was created using LiDAR data with points at 10 m centres. The DTM was linked to the 1D model using a series of link lines that allow water to pass from the 1D domain to the 2D domain when the water level in the channel exceeds the bank levels. The DTM used in the hydraulic model is shown in Figure 5-4 below.



Figure 5-4 Depot / OBG23 LiDAR Derived Digital Terrain Model

A site visit was conducted on the 14th May 2021. Significant features within the channels and in the floodplains were recorded. The site visit aided in determining the Manning's roughness values attributable to the reach. A roughness grid was applied in the model to represent the effects of different surfaces on overland flow. Manning's N values ranged from 0.036 for Agricultural lands to 0.025 to simulate areas of hardstanding.

5.5.1 Key Structures

The inverted siphon masonry arch culvert under the canal (UBG22) appears to be a significant restriction to flow in even minor flood events. The culvert was modelled as 3.54 x 1.42 m high orifice unit.



Figure 5-5 Upstream headwall of UBG22. Arch soffit just visible below water line

5.5.2 Hydraulic Modelling Scenarios

Variations of the hydraulic model were constructed to simulate the existing site conditions and post-development characteristics. Separate simulations were run as to determine flooding at the Depot site and OBG23 as per the joint probability analysis for 10% AEP, 1% AEP and 0.1% AEP events in the current and MRFS climate scenarios. These are discussed below:

Scenario 1 - OBG23 Model – Existing Environment

The Lyreen River has been subject to relatively significant modifications in the vicinity of OBG23 Jacksons Bridge. These are primarily as a result of the rail, canal and motorway crossings. Consultations with landowners have also indicated that the Lyreen was dredged during the course of the motorway construction. It should also be noted that lands directly downstream of the canal culvert appear to have been a deposition area during the motorway construction, resulting increased levels and removal of floodplain area. The aforementioned existing crossings and topography have been represented in the model.

In the current climate scenario the lands directly upstream of UDG22 flood first with flood waters spreading upstream. The culvert under the M4 also exhibits out of bank flooding that builds up south of the M4 before overtopping the road and flowing both north towards the railway and east along the motorway. Having overtopped the M4 flood waters flow overland parallel to the Lyreen. Flood Waters overtop the existing rail line in ~10% AEP event and flow east along the canal. In the 0.1% AEP event flood depths upstream of UDG22 are in excess of 1.5 m. The model indicates that a large portion of the subject area including lands within the footprint of the proposed road and rail embankments are within Flood Zone A. Scenario 1 flood extents are shown in Appendix 12. In the MRFS climate change scenario the flood sources, pathways and receptors are very similar to those seen in the current climate scenario with an overall increase of flood extents in all directions. Volumes of displaced flood waters are indicated in Table 5-12 below.

Table 5-12 Displaced flood volumes at OBG23

Return Period	Flood Waters Displaced (m ³)
Q1000MRFS	35,239.68
Q100MRFS	27,517.90
Q10MRFS	7,547.43

Scenario 1 - OBG23 Model – Post Development

The post development scenario model simulates the effects of the proposed flood risk management measures. These include flood conveyance culverts through the new offline rail embankment and the provision of level for level compensatory storage. Proposed crossings have been sized as to maintain existing flood levels. Bridges soffits are to maintain a freeboard of >300 mm above the 1% AEP (+ climate change) flood level while the minimum rail level will maintain a freeboard of >500 mm above the 0.1% AEP (+ climate change) events.

The post development model shows flood pathways are maintained by the provision of flood conveyance culverts while displaced volumes are accommodated in the compensatory storage areas. The development results in a minor increase in flood levels south of the proposed embankments. Effects are localised to the lands between the proposed development and the N4 with no discernible effect on flood levels at the point where the Lyreen is culverted under the M4 motorway. Effects on the 1 in 100 year flood event (including climate change) are <10 mm throughout the study area. In the 1 in 1000 year (plus climate change scenario) levels were estimated to increase by 70 mm in the immediate vicinity of the proposed watercourse crossings. Nonetheless the overall impact is seen as negligible the existing flood regime at OBG23. Scenario 1 post development flood extents are shown in Appendix 12.

Scenario 1 - OBG23 Model - Water Level Results

Table 5-13 details the calculated extreme water levels and the difference between pre and post-development scenarios at key locations exported from the hydraulic model.

Table 5-13 Water levels Summary

	Climate	Current Scenario (CS)				Mid-Range Future Scenario (MRFS)			
	Development	Pre		Post		Pre		Post	
	AEP	1%	0.1%	1%	0.1%	1%	0.1%	1%	0.1%
Node Label	Description	mOD							
04REA005 30C	Lyreen Upstream of M4 Culvert	61.35	61.51	61.35	61.51	61.41	61.56	61.41	61.56
20LYRE00 150	Lyreen 200m upstream of UDG22	59.89	60.41	59.91	60.47	60.25	60.47	60.27	60.55
20LYRE00 310	Lyreen 130m upstream of UDG22 (location of proposed rail bridge)	59.88	60.40	59.88	60.42	60.24	60.46	60.25	60.49
20LYRE00 600	Lyreen 200m downstream of UDG22	58.75	59.40	58.75	59.41	59.00	59.48	59.00	59.49
01R00700	Ballycaghan Stream 700m upstream of confluence with Lyreen	59.88	60.40	59.89	60.45	60.24	60.46	60.25	60.53
01R00450	Ballycaghan Stream 600m upstream of confluence with Lyreen (location of proposed road bridge)	59.87	60.4	59.89	60.45	60.24	60.46	60.25	60.53
01R00200	Ballycaghan Stream 200m upstream of confluence with Lyreen (location of proposed rail bridge)	59.87	60.40	59.88	60.44	60.25	60.46	60.25	60.53

Scenario 2 – Depot Model – Existing Environment

A review of topography, historic mapping and GSI data indicates that the Ballycaghan stream has been significantly altered and straightened compared to its original course. In the current climate scenario the

lands upstream of the Depot appear to flood first along a route that may have been the historic channel corridor. Field crossings are generally undersized along this reach and are overtopped in relatively frequent events. Overall flood depths are generally low with the deepest ponding in the vicinity of Bailey bridge at a depth of 0.5 m where flood waters appear to be confined by the rail embankment to the north.

The model indicates that a large portion of the subject area including lands within the footprint of the proposed Depot are within Flood Zone A. Scenario 2 flood extents are shown in Appendix 12. In the MRFS climate change scenario the flood sources, pathways and receptors are very similar to those seen in the current climate scenario with an increase in flood extents further downstream towards the Ballycaghan Stream confluence with the Lyreen. Volumes of displaced flood waters are detailed in Table 5-14 below.

Table 5-14 Displaced flood volumes at Depot site

Return Period	Flood Waters Displaced (m ³)
Q1000MRFS	17,136.98
Q100MRFS	13,185.18
Q10MRFS	10,065.05

Scenario 2 - Depot Model – Post Development

The post development scenario model simulates the effects of the proposed flood risk management measures. These include flood conveyance culverts through the new road and rail embankments and the provision of like for like compensatory storage. A minor bund is to be provided along the eastern and southern boundary of the compensatory storage area adjacent to the depot with a height no greater than 1m above existing ground levels.

The post development model shows flood pathways are maintained by the realigned channel around the proposed Depot. Displaced volumes are accommodated in the compensatory storage areas. The development results in a minor increase in flood levels to the west of the Depot along the realigned channel section though these are seen as negligible overall. Scenario 1 post development flood extents are shown in Appendix 12.

Scenario 2 – Depot Model - Water Level Results

Table 5-15 details the calculated extreme water levels and the difference between pre and post-development scenarios at key locations exported from the hydraulic model.

Table 5-15 Water levels Summary

	Climate	Current Scenario (CS)				Mid-Range Future Scenario (MRFS)			
	Development	Pre		Post		Pre		Post	
	AEP	1%	0.1%	1%	0.1%	1%	0.1%	1%	0.1%
Node Label	Description	mOD							
01R02875	Ballycaghan Stream 2875m upstream of confluence with Lyreen	65.40	65.47	65.41	65.48	65.44	65.51	65.44	65.52
01R02550	Ballycaghan Stream 2550m upstream of confluence with Lyreen	63.72	63.79	63.82	63.98	63.77	63.83	63.91	64.06
01R02000	Ballycaghan Stream 2000m upstream of confluence with Lyreen	62.75	62.81	62.18	62.22	62.84	62.86	62.2	62.26

	Climate	Current Scenario (CS)				Mid-Range Future Scenario (MRFS)			
	Development	Pre		Post		Pre		Post	
	AEP	1%	0.1%	1%	0.1%	1%	0.1%	1%	0.1%
Node Label	Description	mOD							
01R01600	Ballycaghan Stream 1600m upstream of confluence with Lyreen	61.57	61.66	61.54	61.69	61.71	61.77	61.63	61.75
01R01009	Ballycaghan Stream 1009m upstream of confluence with Lyreen	60.72	60.75	60.71	60.80	60.8	60.83	60.74	60.82

5.6 Hydraulic Modelling Summary

OBG23 Jacksons Bridge - The findings from the hydraulic analysis indicate that the area surrounding the OBG23 Jackson's bridge is low lying and flow is significantly constrained by the canal culvert UDG22. Extreme fluvial events result in considerable flooding in lands south of the canal and subsequent inundation of the rail line. The model indicates that a large portion of the subject area including lands within the footprint of the proposed rail embankment and access road are within Flood Zone A.

The post development model shows flood pathways are maintained by the provision of flood conveyance culverts while displaced volumes are accommodated in the compensatory storage areas. The development results in a minor increase in flood levels south of the proposed embankments though these are seen as negligible overall.

Depot Site – The hydraulic model indicates that out of bank flow paths flow through the Depot site in multiple locations. Flooding is generally shallow with localised areas of ponding. The model indicates that the proposed Depot is within Flood Zone A. The post development model shows flood pathways are maintained by the realigned channel around the proposed Depot. Displaced volumes are accommodated in the compensatory storage areas. The development results in a minor increase in flood levels to the west of the Depot though these are seen as negligible overall.

Although great care and modern widely-accepted methods have been used in the preparation and interpretation of the hydraulic model, there is inevitably a range of inherent uncertainties and assumptions made during the estimation of design flows and the construction of flood models. The inherent uncertainty necessitates a precautionary approach when interpreting the flood extent and flood depth mapping.

6. FLOOD RISK MANAGEMENT PROPOSALS

Key areas with elevated levels of flood risk have been identified above. This section outlines proposed flood management proposals at each location.

6.1 Dockland Station / Newcomen Area

Existing information indicates that the Docklands / Newcomen area is liable to flood in extreme events with increased flooding likely due to future effects of climate change. Currently the Docklands / Newcomen area is defended to the 0.5%AEP coastal event (1 in 200 year). These municipal defences managed by the local authority and OPW will require adaption to reduce the impact of climate change in the future.

It is envisaged that flooding will be managed at this location through the adoption of flood resilient design and materials, flood warning systems and flood emergency response planning and implementation. Flood forecasting is appropriate as tidal inundation is the primary flood source. Two systems known as Triton and Tidewatch were developed for tidal flood forecasting and warning systems following the coastal flood event in February 2002. Both systems make use of weather and/or surge forecasts in the Irish Sea to provide future predictions of tide levels, with Tidewatch providing forecasts up to five days in advance and Triton two days in advance. The forecasts are used to implement emergency response procedures such as closing of flood gates within existing flood defences. For example, the flood defences along Spencer Dock. On receipt of a flood warning, the Docklands Station flood emergency response plan will be enacted, which should include; preparatory actions (e.g. suspension of services from dockland station), post-flood clean up and reopening procedures. Due to the nature of the flooding (tidal), the impact of flood water displacement is envisaged to be negligible and no compensation is required.

6.2 Broombridge Train Station

Records indicate that flooding at Broombridge was caused by a blockage in the surface water drainage network and as a result flood risk is seen as low at the station. Flood risk at Broombridge will be managed through a combination of standard measures including: drainage maintenance, flood resilient design and materials and flood emergency response planning.

6.3 XG012 Barberstown Level Crossing

The existing level crossing is to be replaced by a bridge over the canal and rail track. The hydraulic assessment detailed within this study has indicated that the proposed works at Barberstown will not affect the existing flood regime and no specific measures are required to manage flood risk at this location.

6.4 Between Maynooth and Kilcock

There are two distinct flooding locations between Maynooth and Kilcock. These are:

6.4.1 OBG23 Jackson Bridge - Rail Track

The hydraulic modelling undertaken as part of this assessment has identified significant flooding in the vicinity of Jackson's Bridge. The track at this location cannot be raised due to potential conflicts with preserving heritage aspects of Jackson's Bridge. In order to provide a sufficient level of protection to the

line, the development has been moved offline on a raised embankment over the floodplain. Proposed crossings have been sized as to maintain existing flood levels. Bridges soffits are to maintain a freeboard of >300 mm above the 1% AEP (+ climate change) flood level while the minimum rail level will maintain a freeboard of >500 mm above the 0.1% AEP (+ climate change) events. A schematic showing proposed measures is presented in Figure 6-1 below. Detailed plan layout and cross sections though compensatory storage areas are presented in Appendix 13.




Figure 6-1 Proposed Compensatory Storage Area - Jacksons Bridge

6.4.2 Bailey’s Bridge - Proposed Depot Site

The Ballycaghan Stream and the proposed Depot lands have been assessed. The proposed development will require a diversion of the existing stream and provisions of compensatory storage. Depot levels will be a minimum of 300 mm above the 0.1% AEP flood level (+ climate change). Residual flood risk will be managed by the implementation of a flood emergency response plan which should form part of the facilities management plan. The depot area and minor watercourse were not covered by the CFRAMS study. A schematic showing proposed measures is presented in Figure 6-2 below. Detailed plan layout and cross sections through compensatory storage areas are presented in Appendix 13.




Figure 6-2 Proposed Compensatory Storage Area - Depot Site

6.5 Dunboyne Tolka River Valley

Available information indicates that the track at this location is not liable to flood in the 0.1% AEP + climate change flood event. However, a long section of the track is effectively surrounded by flood waters in extreme flood events. As such, consideration should be given to the operating procedures in such a flood event. Residual flood risk will be managed by the implementation of flood emergency response planning.

7. JUSTIFICATION TEST

The OPW Guidelines states that primary infrastructure is classified as “highly vulnerable developments”. As per the sequential approach, a justification test is required for the proposed development. In this context, the justification test below has been prepared for the proposed development.:

Table 7-1 Key Planning and Wider Policy Context For Whole Development

1	The development has been zoned or otherwise designated for the particular use or form of development in an operative development plan, which has been adopted or varied taking account of these Guidelines.
	The DART+ Programme is central to the delivery of planning and transportation policy objectives at EU, national, regional and local level. The development has been designated for the particular use in the following key planning and policy documents:
	EU Level
	EU White Paper on Transport: Roadmap to a single European Transport Area - Towards a competitive and resource efficient transport system
	National Policy Context
	Project Ireland 2040 - National Planning Framework – Ireland, Our Plan 2040
	Project Ireland 2040 - National Development Plan, 2018-2027
	National Investment Framework for Transport in Ireland (2021)
	Smarter Travel: A Sustainable Transport Future; 2009-2020
	Strategic Investment Framework for Land Transport (SIFLT)
	Planning Land Use and Transport Outlook 2040 (PLUTO)
	Climate Action Act 2021
	Regional policy Context
	Eastern and Midland Regional Spatial and Economic Strategy 2019-2031
	Integrated Implementation Plan 2019-2024
	Transport Strategy for the Greater Dublin Area 2016-2035
	Greater Dublin Area Cycle Network Plan
	Integrated Implementation Plan 2019-2024
	Local policy context
	<u>Dublin City Development Plan 2016–2022 (under review)</u>
	North Lotts and Grand Canal Dock SDZ Planning Scheme 2014
	Ashtown-Pelletstown Local Area Plan 2014
	<u>Fingal County Development Plan 2017 – 2023</u>
	Hansfield Strategic Development Zone Planning Scheme 2006
	Barnhill Local Area Plan 2018
	Kelystown Local Area Plan 2020
	<u>Kildare County Development Plan 2017 – 2023</u>
	Maynooth Local Area Plan 2013-2019
	Kilcock Local Area Plan 2015-2021
	Leixlip Local Area Plan 2020-2023
	Collinstown Local Area Plan 2010
<u>Meath County Development Plan 2013- 2019</u>	
Dunbooyne, Clonee & Pace Local Area Plan 2009 - 2015	
Site Selection Process (MCA)	

	<p>The Options Selection Report (OSR) presents the outcome of the optioneering process, which has followed a structured and systematic approach to determine the preferred option for the project in an objective manner. The process followed is a Multi-Criteria Analysis (MCA) technique, as recommended by the Common Appraisal Framework (CAF) Guidelines for Transport Projects and Programmes, published by the Department of Transport (2020).</p> <p>The MCA process provides a coherent mechanism for choosing between options on a comparative basis. Each option is characterised under six principal categories as defined within the CAF and compared on a qualitative basis. The principles of the process apply to all options assessment for the project. The mechanism allows for an objective approach to be taken to selection of the most suitable option to be advanced for the project. A summary of the MCA process is presented in Chapter 4 of Volume 2 of the OSR, as has the application of the comparative assessment methodology when appraised against the Project Objectives. Aspects of the process which are particular to individual elements of the project are detailed in each individual Chapter of Volume 2, and should be referred to when reviewing the respective options assessment results. In a number of cases this detailed methodology has been appended to the OSR in an attempt to present a more concise document for public consumption.</p> <p>The Depot location options were originally assessed as part of the <i>Centre Of Excellence Dart Expansion Maintenance Depot Site Location Assessment Report</i> produced in 2019. It was determined that that the depot location is dependent upon operational rail criteria for which Option 2 Maynooth West was ideally suited. The multi-criteria analysis for site selection of the proposed depot was re-examined following identification of the risk of fluvial flooding on the preferred site. It was concluded that Option 2 Maynooth West remains the preferred site for the proposed depot (Refer to DART+ West: Depot Site Selection Supplementary Annex MAY-MDC-GEN-ROUT-RP-Y-0002).</p>
	Justification Test for Development Management
2	The proposal has been subject to a flood risk assessment that demonstrates that:
2-A	The mitigation option suggested will not increase flood risk elsewhere and, if practicable, will reduce overall flood risk;
	Key flood risk areas have been subject to hydraulic analysis to confirm flood risk in the vicinity to the proposed development. This assessment has determined that the proposed development will have a negligible impact on the existing flood regime. The one exception is the development of the proposed Depot and crossing of the Lyreen floodplain where the hydraulic assessment has indicated approximately 50,000 m ³ of flood waters will be displaced. As detailed in section 6, the same amount of compensatory storage has been provided to mitigate this impact. Flood relief culverts are also to be provided through the road and rail embankments to ensure that flows paths are maintained.
2-B	The development proposal includes measures to minimise flood risk to people, property, the economy and the environment as far as reasonably possible;
	Flood management proposals as outlined in section 6 will be integrated into the development and will effectively reduce risks to people, the economy and environment. Key infrastructural elements such as the Depot are to be protected to the 0.1% AEP+ climate change flood event. The Docklands Newcomen area is not indicated to flood in the 0.1% AEP event when existing defences are considered. However, these defences will require adaption in the future to account for the impact of climate change derived sea level rise. The entirety of the scheme will be subject to a flood risk emergency response plan that limits risk to staff and passengers during the operation phase.
2-C	The development proposed includes measures to ensure that residual risks to the area and/or development can be managed to an acceptable level as regards the adequacy of existing flood protection measures or the design, implementation and funding of any future flood risk management measures and provisions for emergency services access.
	The proposed development will be designed to incorporate flood resilient construction measures and materials. The proposed development including flood risk management elements will be subject to a maintenance plan. The maintenance of the proposed development will be undertaken by the relevant competent authority. In the case of a flood event exceeding the design event, the flood emergency response plans will ensure safe egress to appropriate refuge locations.
2-D	The development proposed addresses the above in a manner that is also compatible with the achievement of wider planning objectives in relation to development of good urban design and vibrant and active streetscapes.
	The proposed development will serve existing and future development within Dublin and environs. The proposed project shall reinforce the transportation network, which will assist in achieving strategic planning objectives in the immediate vicinity and the greater Dublin area as a whole. The proposed development will be of a contemporary design in keeping with best urban design practices.

7.1 Justification Test Conclusions

The proposed development has been determined to have satisfied all requirements of the justification test. This includes the identification of flood risk management measures to be implemented as part of the scheme.

8. SITE-SPECIFIC FLOOD RISK ASSESSMENT CONCLUSIONS

This Site-Specific Flood Risk Assessment has considered the local hydrological conditions pertaining to the DART+ West project and identified flood risk areas throughout the development lands. Where development is to be proposed within areas of flood risk, appropriate flood risk management measures have been adopted. The findings of this SSFRA indicate that flood risk to the scheme can be managed with negligible effect on flood risk elsewhere. The proposed development satisfies the requirements of the Justification Test (as described in the OPW's "The Planning System and Flood Risk Management Guidelines for Planning Authorities") and is therefore deemed appropriate for the associated flood risk.

APPENDIX 1. GLOSSARY OF TERMS

Catchment: The area that is drained by a river or artificial drainage system.

Catchment Flood Risk Assessment and Management Studies (CFRAMS): A catchment-based study involving an assessment of the risk of flooding in a catchment and the development of a strategy for managing that risk in order to reduce adverse effects on people, property and the environment. CFRAMS precede the preparation of Flood Risk Management Plans (see entry for FRMP).

Climate change: Long-term variations in global temperature and weather patterns, which occur both naturally and as a result of human activity, primarily through greenhouse gas emissions.

Core of an urban settlement: The core area of a city, town or village which acts as a centre for a broad range of employment, retail, community, residential and transport functions.

Detailed flood risk assessment: A methodology to assess flood risk issues in sufficient detail and to provide a quantitative appraisal of flood hazard and potential risk to an existing or proposed development, of its potential impact on flood elsewhere and of the effectiveness of any proposed measures.

Estuarial (or tidal) flooding: Flooding from an estuary, where water level may be influenced by both river flows and tidal conditions, with the latter usually being dominant.

Flooding (or inundation): Flooding is the overflowing of water onto land that is normally dry. It may be caused by overtopping or breach of banks or defences, inadequate or slow drainage of rainfall, underlying groundwater levels or blocked drains and sewers. It presents a risk only when people, human assets and ecosystems are present in the areas that flood.

Flood Relief Schemes (FRS): A scheme designed to reduce the risk of flooding at a specific location.

Flood Defence: A man-made structure (e.g. embankment, bund, sluice gate, reservoir or barrier) designed to prevent flooding of areas adjacent to the defence.

Flood Risk Assessment (FRA): FRA can be undertaken at any scale from the national down to the individual site and comprises 3 stages: Flood risk identification, initial flood risk assessment and detailed flood risk assessment.

Flood Risk Identification: A desk- based study to identify whether there may be any flooding or surface water management issues related to a plan area or proposed development site that may warrant further investigation.

Flood Hazard: The features of flooding which have harmful impacts on people, property or the environment (such as the depth of water, speed of flow, rate of onset, duration, water quality, etc.).

Floodplain: A flood plain is any low-lying area of land next to a river or stream, which is susceptible to partial or complete inundation by water during a flood event.

Flood Risk: An expression of the combination of the flood probability, or likelihood and the magnitude of the potential consequences of the flood event.

Flood Storage: The temporary storage of excess run-off, or river flow in ponds, basins, reservoirs or on the flood plain.

Flood Zones: A geographic area for which the probability of flooding from rivers, estuaries or the sea is within a particular range.

Fluvial flooding: Flooding from a river or other watercourse.

Groundwater flooding: Flooding caused by groundwater escaping from the ground when the water table rises to or above ground level.

Initial flood risk assessment: A qualitative or semi-quantitative study to confirm sources of flooding that may affect a plan area or proposed development site, to appraise the adequacy of existing information, to provide a qualitative appraisal of the risk of flooding to development, including the scope of possible mitigation measures, and the potential impact of development on flooding elsewhere, and to determine the need for further detailed assessment.

Freeboard: Factor of safety applied for water surfaces. Defines the distance between normal water level and the top of a structure, such as a dam, that impounds or restrains water.

Justification Test: An assessment of whether a development proposal within an area at risk of flooding meets specific criteria for proper planning and sustainable development and demonstrates that it will not be subject to unacceptable risk nor increase flood risk elsewhere. The justification test should be applied only where development is within flood risk areas that would be defined as inappropriate under the screening test of the sequential risk-based approach adopted by this guidance.

Likelihood (probability) of flooding: A general concept relating to the chance of an event occurring. Likelihood is generally expressed as a probability or a frequency of a flood of a given magnitude or severity occurring or being exceeded in any given year. It is based on the average frequency estimated, measured or extrapolated from records over a large number of years and is usually expressed as the chance of a particular flood level being exceeded in any one year. For example, a 1-in-100 or 1% flood is that which would, on average, be expected to occur once in 100 years, though it could happen at any time.

Ordnance Datum (or OD) Malin: is a vertical datum used by an ordnance survey as the basis for deriving altitudes on maps. A spot height may be expressed as AOD for “above ordnance datum”. Usually mean sea level (MSL) is used for the datum. In the Republic of Ireland, OD for the Ordnance Survey of Ireland is Malin Ordnance Datum: the MSL at Portmoor Pier, Malin Head, County Donegal, between 1960 and 1969. Prior to 1970, Poolbeg Ordnance Datum was used: the low water of spring tide at Poolbeg lighthouse, Dublin, on 8 April 1837. Poolbeg OD was about 2.7 metres lower than Malin OD.

Management Train/Treatment Train: the sequence of drainage components that collect, convey, store and treat runoff as it drains through the site.

Mitigation: The term is used to describe an action that helps to lessen the impacts of a process or development on the receiving environment. It is used most often in association with measures that would seek to reduce negative impacts of a process or development.

Pathways: These provide the connection between a particular source (e.g. high river or tide level) and the receptor that may be harmed (e.g. property). In flood risk management, pathways are often ‘blocked’ by barriers, such as flood defence structures, or otherwise modified to reduce the incidence of flooding.

Pluvial flooding: Usually associated with convective summer thunderstorms or high intensity rainfall cells within longer duration events, pluvial flooding is a result of rainfall-generated overland flows which arise before run-off enters any watercourse or sewer. The intensity of rainfall can be such that the run-off totally overwhelms surface water and underground drainage systems.

Regional Planning Guidelines (RPG): These provide the regional context and priorities for applying national planning strategy to each NUTS III region and encourage greater co-ordination of planning policies at the city/county level. RPGs are an important part of the flood policy hierarchy as they can assist in co-ordinating flood risk management policies at the regional level.

Resilience: Sometimes known as “wet-proofing”, resilience relates to how a building is constructed in such a way that, although flood water may enter the building, its impact is minimised, structural integrity is maintained, and repair, drying and cleaning and subsequent reoccupation are facilitated.

Receptors: Things that may be harmed by flooding (e.g. people, houses, buildings or the environment).

Residual risk: The risk which remains after all risk avoidance, substitution and mitigation measures have been implemented, on the basis that such measures can only reduce risk, not eliminate it.

Sequential Approach: The sequential approach is a risk-based method to guide development away from areas that have been identified through a flood risk assessment as being at risk from flooding. Sequential approaches are already established and working effectively in the plan-making and development management processes.

Sustainable Drainage System (SuDS): Drainage systems that are considered to be environmentally beneficial, causing minimal or no long-term detrimental impact.

Site-specific Flood Risk Assessment: An examination of the risks from all sources of flooding of the risks to and potentially arising from development on a specific site, including an examination of the effectiveness and impacts of any control or mitigation measures to be incorporated in that development.


Source: Refers to a source of hazard (e.g. the sea, heavy rainfall).

Strategic Flood Risk Assessment: The assessment of flood risk on a wide geographical area against which to assess development proposed in an area (Region, County, Town).


Vulnerability: The resilience of a particular group of people or types of property or habitats, ecosystems or species to flood risk, and their ability to respond to a hazardous condition and the damage or degree of impact they are likely to suffer in the event of a flood. For example, elderly people may be more likely to suffer injury, and be less able to evacuate, in the event of a rapid flood than younger people.

Source: *The definitions above are sourced from the DoEHLG Guidelines for Planning Authorities on 'The Planning System and Flood Risk Management, 2009' and Ciria 753 "the SuDS Manual".*


APPENDIX 2. CFRAM FLOOD SOURCES




Overview of CFRAMS flood mapping available at Floodinfo.ie. ROD annotations in red indicating development corridor.




CFRAMS Fluvial Flood Mapping of Docklands area. ROD annotations in red indicating development corridor.




CFRAMS Coastal Flood Mapping of Docklands area. ROD annotations in red indicating development corridor.



CFRAMS Coastal Flood Mapping of Newcomen area. ROD annotations in red indicating development corridor.



CFRAMS Fluvial Flood Mapping in vicinity of Leixlip. ROD annotations in red indicating development corridor.



IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE DISCLAIMER, GUIDANCE NOTES AND CONDITIONS OF USE THAT ACCOMPANY THIS MAP.

Legend

- 10% Fluvial AEP Event
- 1% Fluvial AEP Event
- 0.1% Fluvial AEP Event
- Modelled River Centreline
- AFAs Extents
- Embankment
- Wall
- Defenced Area
- Standard of Protection of Flood Defence
- WALLS (Walls / Embankments)
- Node Point
- Node ID

Dart+ Maynooth Line
FINAL

REV: 01 NOTE: Amendment to Flood Def Node Labels DATE: 16/12/2017

CFRAM
CITY OF DUBLIN

OPW
OFFICE OF PUBLIC WORKS

RPS
RISK PREVENTION SERVICES



The Office of Public Works
Jonathan Swift Street
Tullamore
Co. Wick

Enniscorthy House
74 Rochford Road
Dublin
BT 12 6K2

T: +44(0) 28 91 967914
F: +44(0) 28 91 688366
W: www.opw.gov.ie
E: info@opw.gov.ie

Map:
Leixlip Fluvial Flood Extents
Map Type: EXTENT
Source: FLUVIAL
Map Area: HPW
Scenario: CURRENT
Drawn By: F.M.C. Date: 16 December 2017
Checked By: S.P. Date: 16 December 2017
Approved By: G.G. Date: 16 December 2017
Drawing No.: E09LEI_EXFCD_F2_02
Map Series: Page 2 of 8
Drawing Scale: 1:6,000 @A3

CFRAMS Fluvial Flood Mapping in vicinity of Leixlip. ROD annotations in red indicating development corridor.



IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE DISCLAIMER, GUIDANCE NOTES AND CONDITIONS OF USE THAT ACCOMPANY THIS MAP.

Legend

- 10% Fluvial AEP Event
- 1% Fluvial AEP Event
- 0.1% Fluvial AEP Event
- Modelled River Centreline
- AFA Extents
- Embankment
- Wall
- Defended Area
- Standard of Protection of Flood Defence (Walls / Embankments)
- Node Point
- Node Label

Dart+ Maynooth Line FINAL

REV	NOTE	DATE
00	Amendment to Flood Def SOP Label (R/S)	09/12/2017
01	Amendment to Def. Area	16/12/2018



The Office of Public Works
Jonathan Swift Street
Dublin
Co. Meath

Elmwood House T: +44(0)28 90 867914
74 Souther Road T: +44(0)28 90 558296
Ballinacorney T: +44(0)28 90 558296
Ballyvaughan T: +44(0)28 90 558296

Map:
Leixlip Fluvial Flood Extents

Map Type: EXTENT

Source: FLUVIAL

Map Area: HPW

Scenario: CURRENT

Drawn By: F.M.C. **Date:** 16 December 2017

Checked By: S.P. **Date:** 16 December 2017

Approved By: G.O. **Date:** 16 December 2017


Drawing No.: E09LEI_EXFCD_F2_01

Map Series: Page 1 of 8


Drawing Scale: 1:6,000 @A3

Node Label	Water Level (OD) 10% AEP	Flow (m³/s) 10% AEP	Water Level (OD) 1% AEP	Flow (m³/s) 1% AEP	Water Level (OD) 0.1% AEP	Flow (m³/s) 0.1% AEP
09RYEW00000	37.43	1.42	37.87	1.66	38.06	4.25
09RYEW00448	38.79	N/A	38.89	N/A	39.31	N/A
09RYEW00405D	38.20	46.85	38.53	75.44	38.86	107.82
09RYEW00354	38.89	N/A	37.89	N/A	37.81	N/A
09RYEW00323	38.18	46.51	38.48	73.38	38.77	101.86
09RYEW00314	38.54	46.59	38.13	70.86	38.44	112.89


CFRAMS Fluvial Flood Mapping in vicinity of Leixlip. ROD annotations in red indicating development corridor.



CFRAMS Fluvial Flood Mapping in vicinity of Maynooth. ROD annotations in red indicating development corridor.



Node Label	Water Level (OD) 10% AEP	Flow (m³/s) 10% AEP	Water Level (OD) 1% AEP	Flow (m³/s) 1% AEP	Water Level (OD) 0.1% AEP	Flow (m³/s) 0.1% AEP
06LYRE00196	56.78	N/A	57.11	N/A	58.13	N/A
06ROOS00005	56.52	N/A	56.12	N/A	56.87	N/A
06MILF00055	52.04	1.54	52.86	15.22	53.76	19.74
06LYRE00140J	56.13	N/A	55.55	N/A	56.13	N/A
06LYRE00128D	56.85	N/A	57.11	N/A	57.22	N/A
06ROOS00068H	56.56	36.17	56.96	30.56	56.54	30.96
06ROOS00103	55.07	15.15	52.67	35.55	53.28	52.15
06LYRE00128D	51.83	15.33	52.59	34.62	53.42	61.07



IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE DISCLAIMER, GUIDANCE NOTES AND CONDITIONS OF USE THAT ACCOMPANY THIS MAP.

Legend

- 10% Fluvial AEP Event
- 1% Fluvial AEP Event
- 0.1% Fluvial AEP Event
- Modelled River Centreline
- AFA Extents
- Embankment
- Wall
- Defended Area
- Standard of Protection of Flood Defence
- Walls / Embankments
- Node Point
- Node Label

Dart+ Maynooth Line FINAL

REV: 02	NOTE: Amendments to Flood Extent Bridge added in on Page 6	DATE: 02/06/17
REV: 01	NOTE: Addition of downstream zone.	DATE: 12/12/16



OPW **RPS**



The Office of Public Works
Jonathan Swift Street
Dublin
01712 8912

Edmondstown T: +44(0) 28 95 857514
74 Souther Road F: +44(0) 28 95 692306
Dublin W: www.rpsgroup.com
01712 8912 E: www@rpsgroup.com

Map:
Maynooth Fluvial Flood Extents

Map Type:	EXTENT
Source:	FLUVIAL
Map Area:	HPW
Scenario:	CURRENT
Drawn By:	C.C. Date: 1 December 2017
Checked By:	D.J. Date: 1 December 2017
Approved By:	O.G. Date: 1 December 2017
Drawing No.:	E09MAY_EXFCD_F3_07
Map Series:	Page 7 of 11
Drawing Scale:	1:6,000 @ A3

CFRAMS Fluvial Flood Mapping in vicinity of Maynooth. ROD annotations in red indicating development corridor.



IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE DISCLAIMER, GUIDANCE NOTES AND CONDITIONS OF USE THAT ACCOMPANY THIS MAP.

Legend

- 10% Fluvial AEP Event
- 1% Fluvial AEP Event
- 0.1% Fluvial AEP Event
- Modelled River Centreline
- AFA Extents
- Embankment
- Wall
- Defended Area
- Standards of Protection of Flood Defence (Walls / Embankments)
- Node Point
- Node Label

Dart+ Maynooth Line FINAL

REV:	NO:	DATE:
02	Amendments to Flood Extent. Bridge added in on Page 6.	02/09/17
01	Addition of downstream note.	12/12/16

The Office of Public Works
Jonathan Bell Street
Dublin 8
T: +44(0) 29 90 6673/4
F: +44(0) 29 90 6673/6
W: www.rpsgroup.com
E: jbell@rpsgroup.com

Node Label	Water Level (OD) 10% AEP	Flow (m³/s) 10% AEP	Water Level (OD) 1% AEP	Flow (m³/s) 1% AEP	Water Level (OD) 0.1% AEP	Flow (m³/s) 0.1% AEP
06ROES00109	80.72	N/A	80.69	N/A	80.64	N/A
06ROES00043	80.62	3.70	80.58	4.20	80.28	10.70
06ROES00006a	80.77	N/A	80.04	N/A	80.21	N/A
06LYRE000260	80.48	13.82	81.20	17.46	81.36	50.08
06LYRE00334	80.03	N/A	80.53	N/A	80.48	N/A
06LYRE00036	80.61	11.02	80.06	20.34	80.20	36.14
06LYRE00303	80.33	16.88	80.28	20.38	80.47	50.89
06LYRE00280	81.71	18.77	80.25	28.09	80.81	41.89

Map:
Maynooth Fluvial Flood Extents

Map Type: EXTENT

Map Source: FLUVIAL

Map Area: HPW

Scenario: CURRENT

Drawn By: C.C. **Date:** 1 December 2017

Checked By: D.J. **Date:** 1 December 2017


Approved By: G.G. **Date:** 1 December 2017

Drawing No.:
E09MAY_EXFCD_F3_05


Map Series: Page 6 of 11

Drawing Scale: 1:6,000 @A3


CFRAMS Fluvial Flood Mapping in vicinity of Maynooth. ROD annotations in red indicating development corridor.




CFRAMS Fluvial Flood Mapping in vicinity of Maynooth. ROD annotations in red indicating development corridor.




CFRAMS Fluvial Flood Mapping on the Navan Line. ROD annotations in red indicating development corridor.



CFRAMS Fluvial Flood Mapping on the Navan Line. ROD annotations in red indicating development corridor.



CFRAMS Fluvial Flood Mapping on the Navan Line. ROD annotations in red indicating development corridor.



CFRAMS Fluvial Flood Mapping on the Navan Line. ROD annotations in red indicating development corridor.




CFRAMS Pluvial Flood Mapping. ROD annotations in red indicating development corridor.




CFRAMS Pluvial Flood Mapping. ROD annotations in red indicating development corridor.


APPENDIX 3. NATIONAL INDICATIVE FLUVIAL MAPPING



NIFM Flood Extents Dockland Newcomen 1%AEP and 0.1%AEP.




NIFM Flood Extents Barberstown 1%AEP and 0.1%AEP.




NIFM Flood Extents land in vicinity of Maynooth 1%AEP and 0.1%AEP.

APPENDIX 4. ICPSS FLOOD SOURCES




ICPSS Coastal Flood Mapping of Docklands / Newcomen area. ROD annotations in blue indicating development corridor.

APPENDIX 5. IRISH COASTAL WAVE AND WATER LEVEL MODELLING STUDY AND NATIONAL COASTAL FLOOD HAZARD MAPPING




ICWWS Coastal Flood Extents for Docklands Newcomen 0.5%AEP and 0.1%AEP.

APPENDIX 6. OPW NATIONAL FLOOD HAZARD MAPPING




Overview of OPW Flood Hazard Mapping recorded flood events available at Floodinfo.ie. ROD annotations in red indicating development corridor.


APPENDIX 7. DUBLIN CITY DEVELOPMENT PLAN 2016–2022, STRATEGIC FLOOD RISK ASSESSMENT (SFRA)



Overview flood mapping as presented in the Dublin City Council Development Plan Strategic Flood Risk Assessment 2016 -2022. ROD annotations in red indicating development corridor.




— Dart+ Maynooth Line




— Dart+ Maynooth Line

Flood mapping as presented in the Dublin City Council Development Plan Strategic Flood Risk Assessment 2016 -2022. ROD annotations in red indicating development corridor.


APPENDIX 8. FINGAL COUNTY DEVELOPMENT PLAN 2017 – 2023, STRATEGIC FLOOD RISK ASSESSMENT (SFRA) AND BARNHILL STRATEGIC FLOOD RISKS ASSESSMENT (SFRA) OCTOBER 2018




Fingal County Development Plan 2017 – 2023, Strategic Flood Risk Assessment (SFRA). ROD annotations in red indicating development corridor.



Fingal County Development Plan 2017 – 2023, Strategic Flood Risk Assessment (SFRA). ROD annotations in red indicating development corridor.




Fingal County Development Plan 2017 – 2023, Strategic Flood Risk Assessment (SFRA). ROD annotations in red indicating development corridor.




Fingal County Development Plan 2017 – 2023, Strategic Flood Risk Assessment (SFRA). ROD annotations in red indicating development corridor.



Fingal County Development Plan 2017 – 2023, Strategic Flood Risk Assessment (SFRA). ROD annotations in red indicating development corridor.



Fingal County Development Plan 2017 – 2023, Strategic Flood Risk Assessment (SFRA). ROD annotations in red indicating development corridor.




Fingal County Development Plan 2017 – 2023, Strategic Flood Risk Assessment (SFRA). ROD annotations in red indicating development corridor.




<p>PROJECT: BARNHILL SFRA DRAWING: 1000-YEAR CC</p>	<p>STATUS: DRAFT ISSUE: KC1407-FM-1000-CC-V2</p>	<p>V1 - 27/03/18 - Drawn: GP - Checked: YK - Approved: YK V2 - 18/10/18 - Drawn: GP - Checked: YK - Approved: YK</p>	<p>0 100 200 m Scale 1 in 6,500 @ A4</p>	<p>Comhairle Contae Fhine Gall Fingal County Council</p> 
---	--	--	--	--

Barnhill Strategic Flood Risks Assessment (SFRA) October 2018

APPENDIX 9. GEOLOGICAL SURVEY OF IRELAND: TEAGASC SUBSOIL MAPPING




GSI Subsoil Mapping. ROD annotations in red indicating development corridor



GSI Subsoil Mapping. ROD annotations in red indicating development corridor

APPENDIX 10. DUBLIN PLUVIAL STUDY FLOOD MAPPING



IMPORTANT USER NOTE:
 THE VIEWER OF THIS MAP SHOULD REFER TO THE DISCLAIMER, GUIDANCE NOTES AND CONDITIONS OF USE THAT ACCOMPANY THIS MAP.

The Office Of Public Works
 Jonathan Swift Street
 Trim
 Co. Meath



Comhairle Cathrach
 Shille Atha Cliath
 Dublin City Council

Dublin City Council
 Civic Offices
 Wood Quay
 Dublin 8

Project:
 DUBLIN PLUVIAL STUDY (FloodResilientCity)

Map: DUBLIN CITY - PLUVIAL FLOOD EXTENT MAP

Map Type:	EXTENT - 180min Rainfall		
Source:	PLUVIAL		
Map Area:	URBAN		
Scenario:	CURRENT		
Drawn by:	IH	Date:	Aug - 2016
Checked by:	MC	Date:	Aug - 2016
Approved by:	JM	Date:	Aug - 2016
Map No.:	ESDCC_EXPCD_F0_02		
Revision:	F0		
Map Scale:	1:50,000	Plot Scale:	1:1 @ A3



LEGEND

- 10% AEP Pluvial
- 1% AEP Pluvial
- 0.5% AEP Pluvial

IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE DISCLAIMER, GUIDANCE NOTES AND CONDITIONS OF USE THAT ACCOMPANY THIS MAP.

The Office of Public Works
Jonathan Swift Street
Trim
Co. Meath

Cornáiríe Cathrach
Shíle Átha Cliath
Dublin City Council
Dublin City Council
Civic Offices
Wood Quay
Dublin 8

Project:
DUBLIN PLUVIAL STUDY (FloodResilientCity)

Map:	DUBLIN CITY - PLUVIAL FLOOD EXTENT MAP	
Map Type:	EXTENT - 180min Rainfall	
Source:	PLUVIAL	
Map Area:	URBAN	
Scenario:	CURRENT	
Drawn by:	IH	Date: Aug - 2016
Checked by:	MC	Date: Aug - 2016
Approved by:	JM	Date: Aug - 2016
Map No.: E09DCC_EXPCD_F0_01		
Revision: F0		
Map Scale:	1:50,000	Plot Scale: 1:1 @ A3

APPENDIX 11. HYDROLOGICAL CALCULATIONS

- 01 Flow Estimation Spreadsheet - Barberstown
- 02 Barberstown FSSR16 Catchment
- 03 EVD-Gumbel Lyreen Gauge Data
- 04 Flow Estimation Spreadsheet - Lyreen Catchment A
- 05 Flow Estimation Spreadsheet - Lyreen Catchment B
- 06 Flow Estimation Spreadsheet - Lyreen Catchment C
- 07 Flow Estimation Spreadsheet - Lyreen Catchment D
- 08 Lyreen FSSR16 Hydrograph Parameters Catchment A
- 09 Lyreen FSSR16 Hydrograph Parameters Catchment B
- 10 Lyreen FSSR16 Hydrograph Parameters Catchment C
- 11 Lyreen FSSR16 Hydrograph Parameters Catchment D

Flow Estimation Calculations DART+ WEST

Calcs By:	AS
Checked By:	WV
Date:	07/10/2021

Catchment	Total Area (km ²)	SOIL	SAAR	R _{pond}	S1085	L	STMFRQ (F _i)	Estimated Q _{bar} (m ³ /s)			
		(mm)			(m/km)			FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124
Barberstown	6.61	0.30	776.5	29.11	3.3	0	0.453926464	0.727	1.148	0.986	1.024

Factorial Error Factors					Apply Factorial Error Factors to Qbar				Effect of Urbanisation Factor [UF]				
FSR	FSR - 3 Variable	FSSR	IH124 / ICP IH124	Poots Cochrane	FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Urban Area of Catchment	PRr/CIND	CWI	Q _{bar} (urban)	Q _{bar} (rural)
2.17	1.58	1.53	1.65	1.8	1.575	1.814	1.508	1.689	2.00%	27.36	113	1.04	1.04

Growth Factor [GF]	Climate Change Scenario Factor	Arterial Drainage Factor	Evaluation of Baseflow
1:2 years	0.95	0	ANSF = (3.26x10 ⁻⁴).(CWI-125) + (7.4x10 ⁻⁴).RSMD + (3x 10 ⁻³)
1:5 years	1.20	1.2	ANSF = 0.0206 m ³ /s/km ²
1:10 years	1.37	1.3	Baseflow = Area x ANSF
1:50 years	1.74		Baseflow = 0.14 m ³ /s
1:100 years	1.96		
1:200 years	2.14		
1:1000 years	2.74		

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU Small Catchments Methodology
Barberstown	Q2	1.551	1.787	1.486	1.664	1.817709699
	Q5	1.959	2.257	1.877	2.101	2.296054357
	Q10	2.237	2.577	2.143	2.399	2.621328724
	Q50	2.841	3.273	2.721	3.047	3.329278818
	Q100	3.200	3.687	3.065	3.432	3.750222116
	Q200	3.494	4.025	3.347	3.747	4.09463027
	Q1000	4.474	5.154	4.285	4.798	5.242657448

Climate Scenario: MRFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU Small Catchments Methodology
Barberstown	Q2	1.861	2.144	1.783	1.996	2.181251639
	Q5	2.351	2.709	2.252	2.522	2.755265228
	Q10	2.684	3.092	2.571	2.879	3.145594469
	Q50	3.409	3.928	3.265	3.656	3.995134581
	Q100	3.841	4.424	3.678	4.119	4.50026654
	Q200	4.193	4.830	4.016	4.497	4.913556324
	Q1000	5.369	6.185	5.142	5.758	6.291188938

Climate Scenario: HEFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Flood Studies Update
Barberstown	Q2	2.017	2.323	1.931	2.163	2.363022609
	Q5	2.547	2.934	2.440	2.732	2.984870664
	Q10	2.908	3.350	2.785	3.119	3.407727341
	Q50	3.694	4.255	3.538	3.961	4.328062463
	Q100	4.161	4.793	3.985	4.462	4.875288751
	Q200	4.543	5.233	4.351	4.872	5.323019351

FILE=C6C2.dat Flood Modeller VER=5.0.0.7752

***** Flood Modeller

*** HYDROLOGICAL DATA

Catchment: SOUTH00950 (Barberstown)

***** Catchment Characteristics

***** Area : 8.180 km2
 Length : 5.700 km
 Slope : 3.300 m/km
 SAAR : 766.280 mm
 M5-2D : 59.400 mm
 M5-25D : 156.200 mm
 Jenkinsons r : 0.274
 Urban Fraction : 0.000
 RSMD : 0.000 mm
 SPR : 30.000 %

Summary of estimate using Flood Studies Report rainfall-runoff method

***** Using rainfall statistics for Scotland
 and Ireland Estimation of T-year flood

=====

Unit hydrograph time to peak :
 7.938
 hours Instantaneous UH time to peak :
 7.888
 hours Data interval :
 0.100
 hours
 Design storm duration :
 14.100 hours Critical storm duration :
 14.020 hours Flood return period (not
 used) : 1000.000 years Rainfall return
 period :
 1000.000 years M5-14.1 hour/M5-2day :
 0.698
 M*****/M5 : 2.698
 M *****-14.1 (point) : 111.957
 ARF : 0.970
 M *****-14.1(areal) : 108.569 mm
 Design storm depth : 108.569 mm
 CWI : 111.954
 Standard Percentage Runoff :
 30.000

% **Percentage runoff** :
 35.418
 %
Snowmelt rate : 0.000 mm/day
Unit hydrograph peak : 0.227
(m3/s/mm) Quick response hydrograph peak :
 6.856 m3/s
Baseflow : 0.153
 m3/s
Baseflow adjustment : 1.970 m3/s
Hydrograph peak : 5.242 m3/s
Hydrograph adjustment factor : 0.748

Flags

=====

Unit hydrograph flag : FSRUH
 Tp flag : F16TP
Event rainfall flag : FSRER
Rainfall profile flag : WINRP
Percentage Runoff flag : F16PR
Baseflow flag : F16BF
CWI flag : FSRCW

Q	Rank	pp	z	Q
15.5	1	0.04762	3.02023	15.5
14.3	2	0.09524	2.30175	14.3
13.1	3	0.14286	1.86982	13.1
12.2	4	0.19048	1.55443	12.2
12.2	5	0.23810	1.30220	12.2
12.2	6	0.28571	1.08924	12.2
12.1	7	0.33333	0.90272	12.1
11	8	0.38095	0.73486	11
10.6	9	0.42857	0.58050	10.6
9.89	10	0.47619	0.43599	9.89
9.67	11	0.52381	0.29849	9.67
9.52	12	0.57143	0.16570	9.52
9.15	13	0.61905	0.03554	9.15
9.14	14	0.66667	-0.09405	9.14
8.75	15	0.71429	-0.22535	8.75
7.64	16	0.76190	-0.36122	7.64
7.42	17	0.80952	-0.50575	7.42
7.27	18	0.85714	-0.66573	7.27
7.24	19	0.90476	-0.85500	7.24
5.02	20	0.95238	-1.11334	5.02

N= 20

X_{bar}= 10.20


S= 2.65

M= 9.003221 location statistic

B= 2.065593 scale statistic

p	T	K	z	Q
0.990	1.01	-1.52718	-1.52718	5.849
0.900	1.11	-0.83403	-0.83403	7.280
0.700	1.43	-0.18563	-0.18563	8.620
0.500	2	0.36651	0.36651	9.760
0.200	5	1.49994	1.49994	12.101
0.100	10	2.25037	2.25037	13.652
0.050	20	2.97020	2.97020	15.138
0.020	50	3.90194	3.90194	17.063
0.010	100	4.60015	4.60015	18.505
0.005	200	5.29581	5.29581	19.942
0.002	500	6.21361	6.21361	21.838
0.001	1000	6.90726	6.90726	23.271

Extreme Value Analysis - Gumbel



$M = \bar{X} - 0.45005S$ (14-5)

$B = .7797S$ (14-6)

$X = M + B(-\ln(-\ln P))$ (14-7)

M = mode

B = slope

Q = Discharge

Qbar = mean

P = exceedance probability

S = standard deviation

NOTE: For information on the Gumbel distribution, see Bulletin # 17B Guidelines for Determining Flood Flow Frequency.

Flow Estimation Calculations DART+ West Lyreen Catchment A

Calcs By:	WV
Checked By:	
Date:	08/10/2021

Catchment	Total Area (km ²)	SOIL	SAAR	R _{road}	S1085	L	STMPRQ (L)	Estimated Q _{bar} (m ³ /s)			
		(mm)	(mm)		(m/km)			FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124
Lyreen Catchment A	52.00	0.31	776.82	29.12	1.7	0	0.30768006	4.313	8.386	6.254	7.081

Factorial Error Factors					Apply Factorial Error Factors to Qbar				Effect of Urbanisation Factor [UF]				
FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP	Poots Cochrane	FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Urban Area of Catchment	PRr/CIND	CWI	Qbar _(urban)	Qbar _(rural)
2.17	1.58	1.53	1.65	1.8	9.347	13.250	9.568	11.684	0.50%	28.77	113		1.01

Growth Factor [GF]	Climate Change Scenario Factor	Arterial Drainage Factor	Evaluation of Baseflow
1:2 years 0.95	Existing Scenario 0	Do Not Apply	Average Non-Separated Flow
1:5 years 1.20	Mid Range Future Scenario 1.2		ANSF = (3.26x10 ⁻⁴)(CWI-125) + (7.4x10 ⁻⁴). RSMd + (3x 10 ⁻³)
1:10 years 1.37	High End Future Scenario 1.3		ANSF = 0.0206 m ³ /s/km ²
1:50 years 1.74			Baseflow = Area x ANSF
1:100 years 1.96			Baseflow = 1.07 m ³ /s
1:200 years 2.14			
1:1000 years 2.74			

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)					
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Flood Studies Update	CFRAMS Inputs
Lyreen Catchment A	Q2	8.959	12.700	9.171	11.199	9.07	7.77
	Q5	11.317	16.042	11.584	14.146	12.52	11.07
	Q10	12.920	18.315	13.225	16.150	14.78	13.52
	Q50	16.409	23.261	16.797	20.511	19.68	20.32
	Q100	18.484	26.202	18.921	23.105	21.86	23.98
	Q200	20.182	28.608	20.658	25.226	23.94	28.22
	Q1000	25.840	36.630	26.450	32.299	28.75	40.950

Climate Scenario: MRFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)					
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Flood Studies Update	CFRAMS Inputs
Lyreen Catchment A	Q2	10.751	15.240	11.005	13.438	10.884	9.324
	Q5	13.580	19.251	13.901	16.975	15.024	13.284
	Q10	15.504	21.978	15.870	19.380	17.736	16.224
	Q50	19.691	27.913	20.156	24.613	23.616	24.384
	Q100	22.181	31.443	22.705	27.725	26.232	28.776
	Q200	24.218	34.330	24.790	30.272	28.728	33.864
	Q1000	31.008	43.955	31.741	38.759	34.5	49.140

Climate Scenario: HEFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)					
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Flood Studies Update	CFRAMS Inputs
Lyreen Catchment A	Q2	11.647	16.510	11.922	14.558	11.791	10.101
	Q5	14.712	20.855	15.059	18.389	16.276	14.391
	Q10	16.796	23.809	17.193	20.994	19.214	17.576
	Q50	21.332	30.239	21.836	26.665	25.584	26.416
	Q100	24.029	34.063	24.597	30.036	28.418	31.174
	Q200	26.236	37.191	26.856	32.794	31.122	36.686
	Q1000	33.592	47.618	34.386	41.989	37.375	53.235

Flow Estimation Calculations DART+ West Lyreen Catchment B

Calcs By:	WV
Checked By:	
Date:	08/10/2021

Catchment	Total Area (km ²)	SOIL	SAAR	R _{pond}	S1085	L	STMFRQ (F ₁)	Estimated Q _{bar} (m ³ /s)			
			(mm)		(m/km)			FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124
Lyreen Catchment B	4.19	0.37	776.82	29.12	5.4	0	0.715739347	0.747	1.142	1.048	1.069

Factorial Error Factors					Apply Factorial Error Factors to Qbar				Effect of Urbanisation Factor [UF]				
FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Poots Cochrane	FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Urban Area of Catchment	PRr/CIND	CWI	Q _{bar} (urban)	Q _{bar} (rural)
2.17	1.58	1.53	1.65	1.8	1.619	1.805	1.604	1.764	6.00%	34.41	113		1.10

Growth Factor [GF]	Climate Change Scenario Factor	Arterial Drainage Factor	Evaluation of Baseflow
1:2 years 0.95	Existing Scenario 0	Do Not Apply	Average Non-Separated Flow
1:5 years 1.20	Mid Range Future Scenario 1.2		ANSF = (3.26x10 ⁻⁴).(CWI-125) + (7.4x10 ⁻³).RMSD + (3x 10 ⁻³)
1:10 years 1.37	High End Future Scenario 1.3		ANSF = 0.0206 m ³ /s/km ²
1:20 years 1.54			Baseflow = Area x ANSF
1:50 years 1.74			Baseflow = 0.09 m ³ /s
1:100 years 1.96			
1:200 years 2.14			
1:1000 years 2.74			

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment B	Q2	1.695	1.890	1.679	1.847	2.029
	Q5	2.141	2.387	2.121	2.334	2.563
	Q10	2.444	2.726	2.422	2.664	2.926
	Q20	2.748	3.064	2.722	2.995	3.289
	Q50	3.104	3.462	3.076	3.384	3.716
	Q100	3.497	3.899	3.465	3.812	4.185
	Q200	3.818	4.257	3.783	4.162	4.570
	Q1000	4.889	5.451	4.843	5.328	5.851

Climate Scenario: MRFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment B	Q2	2.034	2.268	2.015	2.217	2.434
	Q5	2.569	2.865	2.545	2.800	3.075
	Q10	2.933	3.271	2.906	3.197	3.511
	Q20	3.275	3.691	3.248	3.574	3.947
	Q50	3.725	4.154	3.691	4.060	4.459
	Q100	4.196	4.679	4.157	4.574	5.023
	Q200	4.582	5.109	4.539	4.994	5.484
	Q1000	5.866	6.541	5.812	6.394	7.021

Climate Scenario: HEFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment B	Q2	2.203	2.457	2.183	2.402	2.637
	Q5	2.783	3.104	2.757	3.034	3.331
	Q10	3.178	3.543	3.148	3.463	3.803
	Q20	3.606	4.000	3.598	3.999	4.330
	Q50	4.036	4.500	4.098	4.599	4.830
	Q100	4.546	5.069	4.504	4.955	5.441
	Q200	4.964	5.535	4.918	5.410	5.941
	Q1000	6.355	7.086	6.296	6.927	7.606

Flow Estimation Calculations DART+ West Lyreen Catchment C

Calcs By:	WW
Checked By:	
Date:	08/10/2021

Catchment	Total Area (km ²)	SOIL	SAAR	R _{road}	S1085	L	STMFRQ (F ₁)	Estimated Q _{bar} (m ³ /s)			
		(mm)	(m/km)					FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124
Lyreen Catchment C	6.49	0.30	776.82	29.12	4.3	0	0.154119063	0.560	1.144	0.765	1.021

Factorial Error Factors					Apply Factorial Error Factors to Qbar				Effect of Urbanisation Factor [UF]				
FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP	IH124 / Poots Cochrane	FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Urban Area of Catchment	PRr/CIND	CWI	Qbar _(urban)	Qbar _(rural)
2.17	1.58	1.53	1.65	1.8	1.214	1.807	1.171	1.685	0.50%	27.55	113		1.01

Growth Factor [GF]	Climate Change Scenario Factor	Arterial Drainage Factor	Evaluation of Baseflow
1:2 years 0.95	Existing Scenario 0	Do Not Apply	Average Non-Separated Flow
1:5 years 1.20	Mid Range Future Scenario 1.2		ANSF = (3.26x10 ⁻⁴).(CWI-125) + (7.4x10 ⁻⁴).R5MD + (3x 10 ⁻³)
1:10 years 1.37	High End Future Scenario 1.3		ANSF = 0.0206 m ³ /s/km ²
1:20 years 1.54			Baseflow = Area x ANSF
1:50 years 1.74			Baseflow = 0.13 m ³ /s
1:100 years 1.96			
1:200 years 2.14			
1:1000 years 2.74			

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment C	Q2	1.164	1.732	1.122	1.615	2.664
	Q5	1.471	2.188	1.418	2.040	3.365
	Q10	1.679	2.498	1.618	2.329	3.841
	Q20	1.887	2.808	1.819	2.618	4.318
	Q50	2.132	3.173	2.055	2.958	4.879
	Q100	2.402	3.574	2.315	3.332	5.496
	Q200	2.623	3.902	2.528	3.638	6.000
	Q1000	3.358	4.996	3.237	4.658	7.683

Climate Scenario: MRFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment C	Q2	1.397	2.079	1.347	1.938	3.197
	Q5	1.765	2.626	1.701	2.448	4.038
	Q10	2.015	2.997	1.942	2.795	4.610
	Q50	2.559	3.807	2.467	3.550	5.855
	Q100	2.882	4.288	2.778	3.999	6.595
	Q200	3.147	4.682	3.034	4.366	7.201
	Q1000	4.030	5.995	3.884	5.590	9.219

Climate Scenario: HEFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment C	Q2	1.514	2.252	1.459	2.100	3.463
	Q5	1.912	2.844	1.843	2.652	4.374
	Q10	2.183	3.247	2.104	3.028	4.994
	Q50	2.772	4.124	2.672	3.846	6.343
	Q100	3.123	4.646	3.010	4.332	7.144
	Q200	3.409	5.072	3.286	4.730	7.801
	Q1000	4.365	6.495	4.208	6.056	9.988

Flow Estimation Calculations **DART+ West Lyreen Catchment D**

Calcs By:	WV
Checked By:	
Date:	08/10/2021

Catchment	Total Area (km ²)	SOIL	SAAR	R _{road}	S1085	L	STMPRQ (F ₁)	Estimated Q _{bar} (m ³ /s)			
		(mm)	(mm)	(m/km)				FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124
Lyreen Catchment D	1.35	0.30	776.82	29.12	2.5	0	0.741284349	0.179	0.266	0.264	0.249

Factorial Error Factors					Apply Factorial Error Factors to Qbar				Effect of Urbanisation Factor [UF]				
FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP	IH124 / Poots Cochrane	FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	Urban Area of Catchment	PRr/CIND	CWI	Q _{bar} (urban)	Q _{bar} (rural)
2.17	1.58	1.53	1.65	1.8	0.387	0.421	0.404	0.411	0.00%	27.36	113		1.00

Growth Factor [GF]	Climate Change Scenario Factor	Arterial Drainage Factor	Evaluation of Baseflow
1:2 years 0.95	Existing Scenario 0	Do Not Apply	Average Non-Separated Flow
1:5 years 1.20	Mid Range Future Scenario 1.2		ANSF = (3.26x10 ⁻³)(CWI-125) + (7.4x10 ⁻³). RSM + (3x 10 ⁻³)
1:10 years 1.37	High End Future Scenario 1.3		ANSF = 0.0206 m ³ /s/km ²
1:20 years 1.54			Baseflow = Area x ANSF
1:50 years 1.74			Baseflow = 0.03 m ³ /s
1:100 years 1.96			
1:200 years 2.14			
1:1000 years 2.74			

Climate Scenario: Existing	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment D	Q2	0.368	0.400	0.384	0.390	0.543
	Q5	0.464	0.505	0.485	0.493	0.686
	Q10	0.530	0.576	0.554	0.563	0.783
	Q20	0.596	0.648	0.623	0.633	0.880
	Q50	0.673	0.732	0.703	0.715	0.994
	Q100	0.758	0.825	0.792	0.805	1.120
	Q200	0.828	0.900	0.865	0.879	1.223
	Q1000	1.060	1.153	1.108	1.126	1.566

Climate Scenario: MRFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment D	Q2	0.441	0.480	0.461	0.468	0.651
	Q5	0.557	0.606	0.582	0.592	0.823
	Q10	0.636	0.692	0.665	0.675	0.940
	Q50	0.808	0.879	0.844	0.858	1.193
	Q100	0.910	0.990	0.951	0.966	1.344
	Q200	0.994	1.080	1.038	1.055	1.468
	Q1000	1.272	1.383	1.329	1.351	1.879

Climate Scenario: HEFS	Design Q	Apply Urbanisation Factor, Growth Factor, Arterial Drainage Factor (m ³ /s)				
		FSR	FSR - 3 Variable	FSSR No.6	IH124 / ICP IH124	FSU 4.2 Small Catchments
Lyreen Catchment D	Q2	0.478	0.520	0.499	0.507	0.706
	Q5	0.604	0.656	0.631	0.641	0.892
	Q10	0.689	0.749	0.720	0.732	1.018
	Q50	0.875	0.952	0.914	0.929	1.293
	Q100	0.986	1.072	1.030	1.047	1.456
	Q200	1.076	1.171	1.125	1.143	1.590
	Q1000	1.378	1.499	1.440	1.463	2.036

FILE=5AD6.dat Flood Modeller VER=5.0.0.7752

***** Flood Modeller

*** HYDROLOGICAL DATA

Catchment: 04REA00717 (Catchment A)

***** Catchment Characteristics

***** Area : 52.002 km2
 Length : 24.800 km
 Slope : 1.907 m/km
 SAAR : 776.860 mm
 M5-2D : 56.200 mm
 M5-25D : 157.900 mm
 Jenkinsons r : 0.279
 Urban Fraction : 0.000
 RSMD : 0.000 mm
 SPR : 31.000 %

Summary of estimate using Flood Studies Report rainfall-runoff method

***** Using rainfall statistics for Scotland
 and Ireland Estimation of T-year flood

=====

Unit hydrograph time to peak :
 13.209 hours Instantaneous UH time to
 peak : 13.159 hours Data interval :
 0.100

hours

Design storm duration :
 23.100 hours Critical storm duration :
 23.470 hours Flood return period (not
 used) : 1000.000 years Rainfall return
 period :
 1000.000 years M5-23.1 hour/M5-2day :
 0.829

M*****/M5 : 2.622
 M *****-23.1 (point) : 122.214
 ARF : 0.954
 M *****-23.1(areal) : 116.632 mm
 Design storm depth : 116.632 mm
 CWI : 113.223
 Standard Percentage Runoff :
 31.000
 % Percentage runoff :
 37.438

%
Snowmelt rate : 0.000 mm/day
Unit hydrograph peak : 0.866
(m3/s/mm) Quick response hydrograph peak :
 29.867 m3/s
Baseflow : 1.013
 m3/s
Baseflow adjustment : 4.000 m3/s
Hydrograph peak : 40.950 m3/s
Hydrograph adjustment factor : 1.326

Flags

=====

Unit hydrograph flag : FSRUH
Tp flag : F16TP
Event rainfall flag : FSRER
Rainfall profile flag : WINRP
Percentage Runoff flag : F16PR
Baseflow flag : F16BF
CWI flag : FSRCW

FILE=F303.dat Flood Modeller VER=5.0.0.7752

***** Flood Modeller

*** HYDROLOGICAL DATA

Catchment: 01R03000 (Catchment B)

***** Catchment Characteristics

***** Area : 4.190 km2
 Length : 4.700 km
 Slope : 5.360 m/km
 SAAR : 776.500 mm
 M5-2D : 56.200 mm
 M5-25D : 157.900 mm
 Jenkinsons r : 0.279
 Urban Fraction : 0.060
 RSMD : 0.000 mm
 SPR : 37.000 %

Summary of estimate using Flood Studies Report rainfall-runoff method

***** Using rainfall statistics for Scotland
 and Ireland Estimation of T-year flood

=====

Unit hydrograph time to peak :
 6.081
 hours Instantaneous UH time to peak :
 5.581
 hours Data interval :
 1.000
 hours
 Design storm duration :
 11.000 hours Critical storm duration :
 10.803 hours Flood return period (not
 used) : 100.000 years Rainfall return
 period :
 100.000 years M5-11.0 hour/M5-2day :
 0.646
 M100.0/M5 : 1.800
 M 100.0-11.0 (point) : 65.361
 ARF : 0.973
 M 100.0-11.0(areal) : 63.625 mm
 Design storm depth : 63.625 mm
 CWI : 113.180
 Standard Percentage Runoff :
 37.000

% **Percentage runoff** :
 37.000
 %
Snowmelt rate : 0.000 mm/day
Unit hydrograph peak : 0.152
(m3/s/mm) Quick response hydrograph peak :
 2.774 m3/s
Baseflow : 0.081
 m3/s
Baseflow adjustment : 0.300 m3/s
Hydrograph peak : 4.190 m3/s
Hydrograph adjustment factor : 1.467

Flags

=====

Unit hydrograph flag : FSRUH
 Tp flag : R124TP
Event rainfall flag : FSRER
Rainfall profile flag : WINRP
Percentage Runoff flag : OBSPR
Baseflow flag : F16BF
CWI flag : FSRCW

FILE=65CA.dat Flood Modeller VER=5.0.0.7752

***** Flood Modeller

*** HYDROLOGICAL DATA

Catchment: 02R00923 ((Catchment C)

***** Catchment Characteristics

***** Area : 6.490 km2
 Length : 6.100 km
 Slope : 4.300 m/km
 SAAR : 776.500 mm
 M5-2D : 56.200 mm
 M5-25D : 157.900 mm
 Jenkinsons r : 0.279
 Urban Fraction : 0.000
 RSMD : 0.000 mm
 SPR : 30.000 %

Summary of estimate using Flood Studies Report rainfall-runoff method

***** Using rainfall statistics for Scotland
 and Ireland Estimation of T-year flood

=====

Unit hydrograph time to peak :
 7.339
 hours Instantaneous UH time to peak :
 7.289
 hours Data interval :
 0.100
 hours
 Design storm duration :
 13.100 hours Critical storm duration :
 13.038 hours Flood return period (not
 used) : 50.000 years Rainfall return
 period :
 50.000 years M5-13.1 hour/M5-2day :
 0.685
 M 50.0/M5 : 1.567
 M 50.0-13.1 (point) : 60.350
 ARF : 0.971
 M 50.0-13.1(areal) : 58.612 mm
 Design storm depth : 58.612 mm
 CWI : 113.180
 Standard Percentage Runoff :
 30.000

% **Percentage runoff** :
 30.000
 %
Snowmelt rate : 0.000 mm/day
Unit hydrograph peak : 0.195
(m3/s/mm) Quick response hydrograph peak :
 2.686 m3/s
Baseflow : 0.126
 m3/s
Baseflow adjustment : 0.750 m3/s
Hydrograph peak : 5.500 m3/s
Hydrograph adjustment factor : 1.955

Flags

=====

Unit hydrograph flag : FSRUH
 Tp flag : F16TP
Event rainfall flag : FSRER
Rainfall profile flag : WINRP
Percentage Runoff flag : OBSPR
Baseflow flag : F16BF
CWI flag : FSRCW

FILE=C170.dat Flood Modeller VER=5.0.0.7752

***** Flood Modeller

*** HYDROLOGICAL DATA

Catchment: Catch-C-LAT (Catchment D)

***** Catchment Characteristics

***** Area : 1.349 km2
 Length : 2.882 km
 Slope : 2.520 m/km
 SAAR : 776.500 mm
 M5-2D : 56.200 mm
 M5-25D : 157.900 mm
 Jenkinsons r : 0.279
 Urban Fraction : 0.000
 RSMD : 0.000 mm
 SPR : 30.000 %

Summary of estimate using Flood Studies Report rainfall-runoff method

***** Using rainfall statistics for Scotland
 and Ireland Estimation of T-year flood

=====

Unit hydrograph time to peak :
 7.368
 hours Instantaneous UH time to peak :
 7.318
 hours Data interval :
 0.100
 hours
 Design storm duration :
 13.100 hours Critical storm duration :
 13.089 hours Flood return period (not
 used) : 50.000 years Rainfall return
 period :
 50.000 years M5-13.1 hour/M5-2day :
 0.685
 M 50.0/M5 : 1.567
 M 50.0-13.1 (point) : 60.350
 ARF : 0.983
 M 50.0-13.1(areal) : 59.329 mm
 Design storm depth : 59.329 mm
 CWI : 113.180
 Standard Percentage Runoff :
 30.000

% Percentage runoff	:	30.622
%		
Snowmelt rate	:	0.000 mm/day
Unit hydrograph peak	:	0.040
(m3/s/mm) Quick response hydrograph peak	:	0.575 m3/s
Baseflow	:	0.026
m3/s		
Baseflow adjustment	:	0.000 m3/s
Hydrograph peak	:	0.674 m3/s

Hydrograph adjustment factor : 1.120

Flags

=====


Unit hydrograph flag : FSRUH
Tp flag : R124TP
Event rainfall flag : FSRER
Rainfall profile flag : WINRP
Percentage Runoff flag : F16PR
Baseflow flag : F16BF
CWI flag : FSRCW

APPENDIX 12. FLOOD EXTENT MAPPING



<table border="1"> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </table>																				Client 	Project 	Drawing Title LC05 - Barberstown Existing & Post Development Current Climate Scenario
PRODUCED BY: [] REVIEWED BY: [] APPROVED BY: []				Consultant 	Scale: 1:2,500 	Drawing Number Project Originator Discipline Location Type Role Number Phase MAY MDC GEO LC05 DR D 1550 B																
© 2021 IJD IDOM. This drawing is confidential and the copyright is owned by IJD IDOM. This drawing is not to be reproduced or otherwise registered or used in any way without the prior permission of IJD IDOM.				Date: October 2021	Job No: PF101066	Status: 95 - Work In Progress	Rev: V 05	Sheet: 1 of 2														





REV	DATE	DESCRIPTION	PRODUCED BY	REVIEWED BY	APPROVED BY

© IROD 2021. This drawing is not to be used and the copyright in it is owned by IROD. The drawing shall not be altered, copied, or otherwise reproduced in whole or in part, or used for any purpose other than the specific project of the client.
 IROD is a registered company under the Companies Act 2014. IROD is a member of the Chartered Institution of Building Services Engineers (CIBSE).
 All drawings are to be read and used in accordance with the IROD Terms and Conditions of Use. IROD is not liable for any loss or damage arising from the use of this drawing.
 IROD is a member of the Chartered Institution of Building Services Engineers (CIBSE).

Client:

Consultant:

Project:

Drawing Title: **OBG23**
Existing Current Climate Scenario

Scale: 1:5,000	Drawing Number Project Originator Discipline Location Type Role Number Phase
	MAY MDC GEO OBG23 DR D 1650 B
Date: October 2021	Job No: RY101585 Status: 3D - Work In Progress Rev: V 03 Sheet: 1 of 2



REV	DATE	DESCRIPTION	PRODUCED BY	REVIEWED BY	APPROVED BY

© 2021. All rights reserved. This drawing is confidential and the copyright in it is owned by IDOM. This drawing and the information contained in it are intended for the use of the client only and are not to be used for any other purpose without the prior written consent of IDOM. IDOM is not responsible for any errors or omissions in this drawing. All information is provided as is and without any warranty. All information is provided as is and without any warranty. All information is provided as is and without any warranty.

Client:

Consultant:


Project:

Drawing Title: **OBG23**
Existing Climate Change Scenario

Scale: 1:5,000
0 500 1,000 2,000

Drawing Number	Project	Discipline	Location	Type	Role	Number	Phase
MAY	MDC	GEO	OBG23	DR	D	1650	B

Date	Job No.	Status	Rev.	Sheet
October 2021	FF101086	3D - Work In Progress	V 03	2 of 2



<table border="1"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> <th>PRODUCED BY</th> <th>REVIEWED BY</th> <th>APPROVED BY</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		REV	DATE	DESCRIPTION	PRODUCED BY	REVIEWED BY	APPROVED BY							Client 	Project 	Drawing Title Depot Existing Climate Change Scenario
REV	DATE	DESCRIPTION	PRODUCED BY	REVIEWED BY	APPROVED BY											
Consultants 		Scale 1:5,000 	Drawing Number Project Originator Discipline Location Type Role Number Phase MAY MOC GEO DEPM OR D 1650 B													
Date: October 2021 Job No: P1101086 Status: 90 - Work in Progress Rev: V 03 Sheet: 2 of 2		© 2021 IDOM. All rights reserved. No part of this document may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of IDOM.														



REV.	DATE	DESCRIPTION	PRODUCED BY	REVIEWED BY	APPROVED BY

© 2021 IDOM (2021). This drawing is confidential and the copyright in it is owned by IDOM. This drawing may not be copied, reprinted, or otherwise reproduced in whole or in part or used for any purpose without the prior written consent of IDOM.
 IDOM and its affiliates shall not be held liable for any errors or omissions in this drawing. IDOM shall not be held liable for any errors or omissions in this drawing.
 IDOM shall not be held liable for any errors or omissions in this drawing. IDOM shall not be held liable for any errors or omissions in this drawing.
 All drawings are in metric and shall be to the latest metric (SI) units unless otherwise stated. IDOM shall not be held liable for any errors or omissions in this drawing.

Client

Consultant

Project

Drawing Title

OBG23
Post Development Current Climate Scenario

Scale: 1:5,000

Drawing Number	Project	Originator	Discipline	Location	Type	Role	Number	Phase

Date	Job No.	Status	Rev.	Sheet
October 2021	17101598	50 - Work In Progress	V.03	1 of 2



<table border="1"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> <th>PRODUCED BY</th> <th>REVIEWED BY</th> <th>APPROVED BY</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		REV	DATE	DESCRIPTION	PRODUCED BY	REVIEWED BY	APPROVED BY							<p>Client</p>	<p>Project</p>	<p>Drawing Title</p> <p>OBG23 Post Development Climate Change Scenario</p>
REV	DATE	DESCRIPTION	PRODUCED BY	REVIEWED BY	APPROVED BY											
<p>© 2021 IDOM. This drawing is confidential and the copyright is owned by IDOM. This drawing may not be used for any other project without the prior written consent of IDOM.</p> <p>© 2021 IDOM. This drawing is confidential and the copyright is owned by IDOM. This drawing may not be used for any other project without the prior written consent of IDOM.</p> <p>© 2021 IDOM. This drawing is confidential and the copyright is owned by IDOM. This drawing may not be used for any other project without the prior written consent of IDOM.</p>		<p>Consultant</p>	<p>Scale:</p> <p>1:5,000</p>	<p>Drawing Number Project Originator Discipline Location Type Role Number Phase</p> <p>MAY MDC GEO OBG23 DR D 1650 B</p> <p>Date: October 2021 Job No: P1101086 Status: 00 - Work In Progress Rev: V 03 Sheet: 2 of 2</p>												



<p>Client</p>		<p>Project</p>	<p>Drawing Title</p> <p>Depot Post Development Current Climate Scenario</p>
<p>Consultant</p>		<p>Scale:</p> <p>1:5,000</p> <p>0 500 1,000 2,000</p>	<p>Drawing Number Project Originator (Discipline) Location Type Role Number Phase</p> <p>MAY MDC GEO DEPM DR D 1650 B</p> <p>Date: October 2021 Job No: P/101086 Status: 80 - Work In Progress Rev: V 03 Sheet: 1 of 2</p>




<p>REV. DATE DESCRIPTION PRODUCED BY/REVIEWED BY/ APPROVED BY</p>		<p>Client</p>	<p>Project</p>	<p>Drawing Title</p> <p>Depot Post Development Climate Change Scenario</p>																
<p>CONSULTANT</p>		<p>Scale: 1:15,000</p>		<p>Drawing Number</p> <table border="1"> <tr> <th>Project</th> <th>Originator</th> <th>Discipline</th> <th>Location</th> <th>Type</th> <th>Role</th> <th>Number</th> <th>Phase</th> </tr> <tr> <td>MAY</td> <td>MDC</td> <td>GEO</td> <td>DEPM</td> <td>DR</td> <td>D</td> <td>1650</td> <td>B</td> </tr> </table>	Project	Originator	Discipline	Location	Type	Role	Number	Phase	MAY	MDC	GEO	DEPM	DR	D	1650	B
Project	Originator	Discipline	Location	Type	Role	Number	Phase													
MAY	MDC	GEO	DEPM	DR	D	1650	B													
<p>DATE: October 2021</p>		<p>JOB NO: RFD1586</p>	<p>STATUS: 80 - Work In Progress</p>	<p>Rev: V 03</p> <p>Sheet: 2 of 2</p>																

APPENDIX 13. COMPENSATORY STORAGE AREAS



Client 		Project 		Drawing Title GENERAL DESIGN COMPENSATORY STORAGE AREAS LAYOUT PLAN	
Consultant 		Scale 1:1000 @ A1 1:2000 @ A3 		Drawing Number Project Originator Discipline Location Type Role Number Phase MAY MDC GEN SC07 DR Y 0001 C Date Job No. Status Rev. Sheet April 2022 P1101088 P1-Approved & accepted V01 2 of 2	



REV	DATE	DESCRIPTION	INT	COI	TMK
V01	April 2022	PLANNING ISSUE			

PRODUCED BY: [] REVIEWED BY: [] APPROVED BY: []

© 2022 IDOM. This work is confidential and the copyright is reserved by IDOM. This drawing must not be used for any other project without the prior written consent of IDOM. All drawings are to be used as a guide only. IDOM shall not be held responsible for any errors or omissions. All drawings are to be used as a guide only. IDOM shall not be held responsible for any errors or omissions. All drawings are to be used as a guide only. IDOM shall not be held responsible for any errors or omissions.

Client:

Consultant:


Project:

Drawing Title: GENERAL DESIGN COMPENSATORY STORAGE AREAS LAYOUT PLAN

Drawing Number: MAY MDC GEN SC07 DR Y 0001 C


Scale: 1:1000 @ A1 1:2000 @ A3

Date: April 2022 Job No: P1121086 Status: F1-Approved & accepted Rev: V01 Sheet: 2 of 2



DEPOT AXIS

Client		Project		Drawing Title	
				GENERAL DESIGN COMPENSATORY STORAGE AREAS CROSS SECTIONS	
Consultant				Scale: 1:1000 @ A1 1:2000 @ A3 Drawing Number: MAY MDC GEN SC07 DR Y 0002 C Date: April 2022 Job No: P101086 Status: F1-Approved & accepted Rev: V01 Sheet: 1 of 3	



REV	DATE	DESCRIPTION	BY	CHK	TRK
V01	April 2022	PLANNING ISSUE			
PRODUCED BY			REVIEWED BY		
APPROVED BY			APPROVED BY		

© All rights reserved. This drawing is confidential and the copyright in it is owned by IARL. This drawing must not be copied, reproduced or otherwise used without the express written consent of IARL. All rights reserved. This drawing is confidential and the copyright in it is owned by IARL. This drawing must not be copied, reproduced or otherwise used without the express written consent of IARL.

Client

Consultant

Project

Drawing Title


GENERAL DESIGN
COMPENSATORY STORAGE AREAS
CROSS SECTIONS

Scale: 1:1000 @ A1 1:2000 @ A3

Drawing Number | Project | Originator | Discipline | Location | Type | Role | Number | Phase

MAY | MDC | GEN | SC07 | DR | Y | 0002 | C

Date: April 2022 | Job No: P101086 | Status: F1-Approved & accepted | Rev: V01 | Sheet: 2 of 3



OBG23 - AXIS 2

<table border="1"> <tr> <td>REV</td> <td>DATE</td> <td>DESCRIPTION</td> <td>BY</td> <td>CHK</td> <td>TMR</td> </tr> <tr> <td>001</td> <td>April 2022</td> <td>PLANNING ISSUE</td> <td></td> <td></td> <td></td> </tr> </table>				REV	DATE	DESCRIPTION	BY	CHK	TMR	001	April 2022	PLANNING ISSUE				Client 	Project 	Drawing Title GENERAL DESIGN COMPENSATORY STORAGE AREAS CROSS SECTIONS
REV	DATE	DESCRIPTION	BY	CHK	TMR													
001	April 2022	PLANNING ISSUE																
<small> © 2022 IDOM, this drawing is copyrighted and the copyright is held by Iarnród Éireann. This drawing must not be copied, reproduced or otherwise transmitted in any form or used for any purpose without the prior permission of Iarnród Éireann. Iarnród Éireann is not responsible for any errors or omissions in this drawing. Iarnród Éireann is not responsible for any errors or omissions in this drawing. All drawings are to be read and taken in full accordance with the Iarnród Éireann Project Contract. All dimensions are in millimetres unless otherwise stated. </small>				Consultant 	Drawing Number Project Originator Discipline Location Type Role Number Phase MAY MDC GEN SC07 DR Y 0002 C	Date Job No. Status Rev Sheet April 2022 P1101066 F1-Approved & accepted V01 3 of 3												

IDOM

PROD
ROUGHAN & O'DONOVAN